



GLEN N. RUPE

OIL PRODUCER

PEKAREK #6 - NW NW NE of Section 20-14S-10W,
ELLSWORTH COUNTY, KANSAS

Page 1
DICK FOLEY, Geologist

October 24, 1969 - Laughlin-Simmons elevation is 1689' Ground
est. 1694' Kelley Bushing

October 26, 1969 - Red Tiger Drilling Company moved in Rotary Tools and
Spudded at 1:15 p.m.
Set 8 5/8" Surface Casing at 268' cemented with
175 Sacks Common Sunset. Cement circulated.
Plug was down at 4:45 p.m.

October 27, 1969 - Top Anhydrite 472' - 505' or +1222'.
Drilling at 515' at 7:00 a.m.

At Anhydrite level this Well is 14' higher than #5
PEKAREK and 1' lower than the PRINC #1.

October 28, 1969 - Drilling at 1700' at 7:00 a.m.

October 29, 1969 - Drilling at 2428' at 8:00 a.m.

Grand Haven Lime 2075'

Tarkio Lime 2157'

Howard 2366'

Topeka 2404' * corrected to 2401'

October 30, 1969 - Drilling at 2585'

Took Drill Stem Test #1 from 2433' to 2455' -
Open 90 min.; shut in 60 min.; open 60 min.;
shut in 60 min.

Recovered 1900' gas in Pipe
62' Oil spotted Mud

Initial Shut In Pressure 400#

Initial Flow Pressure 88#

Final Flow Pressure 97#

Final Shut In Pressure 418#

October 31, 1969 - Circulating for Samples at 2847'

3:30 p.m. - Completed Drill Stem Test #2 from
2825' to 2847' - Open 60 min.; shut in 60 min.;
open 60 min.; shut in 60 min. Had weak blow for
15 min. and died. Recovered 15' Mud with few small
Oil Spots.

Initial Shut In Pressure 177#

Initial Flow Pressure 44#

Final Flow Pressure 53#

Final Shut In Pressure 151#

Going back to bottom to drill to the 80' Zone.

November 3, 1969 - On November 1st drilled both 80' and 90' Zones--
had no show of oil in either Zone.

Rotary Total depth 2915' - plugging and abandoning.

Plugged hole with 25 sacks cement at 260'; mud to 40';

1/2 sack Hulls and plugged with 10 sacks Cement;

2 sacks cement in Rat hole. Plugging was completed

4:25 a.m. November 1st.

Felt at best, the Topeka and Lansing "B" Zone--would make
a small producing well



GLEN N. RUPE

OIL PRODUCER

222 Brown Building — Wichita, Kansas 67202 — AM 2-3748

PEKAREK #6 - NW NW NE of Section 20-14S-10W,
Ellsworth County Kansas

Page 2

November 4, 1969

Geologist, Dick Foley advised a correction on Topeka
from 2404' to read 2401'

"Wilson Creek" Topeka	2441'
Heebner	2693'
Brown Lime	2775'
Lansing	2803'
30' Zone	2829'

Above are Sample Tops.

Rotary Total Depth 2915'

Well "Dry and Abandon".

No Log Run

PEKAREK #6 - NW NW NE of Section 20-14S-10W,
ELLSWORTH COUNTY, KANSAS

D E A

11/1/69

Drlg. Contractor: Red Tiger (EO 3-2371)

(Drcky Foley)

10/21 Ordered elevation from Laughlin-Simmons and they will run tomorrow or Thursday this week.

10/24 Laughlin-Simmons called and elevation is 1689' Ground level. (Elevation 10/29/69)

10/24 Red Tiger filing Intent to Drill today. (Lapping & Lay same as #5 Pekarek 7/12/22)

10/26 Red Tiger moved in -- spudded at 1:15 p.m. Cut 268' of 12 1/4" hole. (Slope Test 268' = 3/4 degree). Ran 7 Jts. 8 5/8" 8 Rd. Thd. 20# Range 3=259.99'. Set at 268' cemented with 175 sacks common Sunset Cement-circulated. Plug down at 4:45 p.m.

Drilled plug at 11:45 p.m.

10/27 Top Anhydrite 472' - 505' or +1222'

Drilling at 515' at 7:00 a.m.

At Anhydrite level this Well is 14' higher than #5 and 1' lower than PRINC #1

*Note--We won't produce the #5 PEKAREK until November 1st, so we can start the month out under the new Royalty change.

1260' at 3:00 p.m.

10/28 Drilling at 1700'.

10/29 Dick Foley, Geologist/ called following

Grand Haven Line	2075'
Tarkio Line	2157'
Howard	2366'
Topeka	2404'

Drilling at 2428' at 8:00 a.m.

10/30 Drilling at 2585'

DST #1 from 2433' to 2455' - Open 90 min.; shut in 60 min.; open 60 min.; shut in 60 min.

Recovered 1900' gas in pipe

62' Oil Spotted Mud

Initial Shut In Pressure 400#

Initial Flow 88#

Final Flow 97#

Final Shut In Pressure 418#

10/31 Circulating for Samples at 2847'

Preparing to take DST #2 from 2825' to 2847'

LANSING 2804' or -1110'

(Well running 5' lower than #5 PEKAREK at Lansing level.)

Completed DST #2 from 2825' to 2847' - Open 60, Shut In 60, Open 60

Shut in 60--recovered 15' mud few small oil spots

weak blow for 15 min and died (Going back to bottom to drill to the 80' Zone)

60 min shut in - ISIP 177#

IF 44#

FR 52#

264-1361
FIELDS
GEMINT
CORSKI
RNH INC
RUNNELS
SCOTT
WOMER
Am-4-1371

800 190' down 10-100 ft
L 1 P.L. 2890' 70
L 16' 1/2 100 ft
L 16'

2006-05-23

C. C. 25 of 1260; - 140' 1/2 down hole C, 10' 11
2 Sacks in net hole - 12
Complete 4/25/11 11/1/17 13