

THE ELDORADO REFINING CO.
Tena Stratmann No. 1.

SEC 32 T. 14 R. 11W.
SW SE SE


Plotted

JTC

County. Russell.

Total Depth. 3250.
Comm. 9-8-34 Comp. 11-2-34
Shot or Treated.
Contractor. Yankey-Stearns.
Issued. 12-1-34.

DEC 1 1934



CASING.

15 1/2" 40'5", 8" 2232' UR 2350 reamed 2357 UR 2427
133/8" 553' 6" 2798 lowered 21' set 2876
10" 1815' lowered to 1833

Elevation.
Production. DRY.

Figures Indicate Bottom of Formations.

surface	9	lime grey	1358	lime	2475
quick sand	16	slate & shells	1375	shale	2477
clay yellow	30	shale	1384	hole corrected 2707 to	2743
sand	45	lime	1395	lime	2775
shale white	53	shale blue	1405	shale	2783
sand	62	shale	1415	lime	2805
red rock	94	lime	1453	shale brown	2807
shale blue	104	red rock	1480	lime	2812
red rock	130	lime	1605	shale green	2817
slate	160	slate blue	1623	lime	2819
red rock	166	lime	1680	shale green	2820
sand broken	175	LBWPHR 1595-1600		lime shell & shale	2873
shale blue	194	shale	1704	lime	2884
shale light	211	lime	1728	shale blue	2887
sand broken	218	hole caving.		lime	2940
4 BW 165-75		shale blue	1740	shale	2950
shale blue	227	red rock	1752	lime	3062
lime	230	lime	1780	600' water in hole.	
sand	238	shale blue	1788	slate blue	3066
shale blue & iron. 2254		lime	1800	lime	3080
lime hard	262	red rock	1806	slate dark	3088
sand and lime	271	lime	1816	hole caving 3062	
sand	274	hole caving 1800		lime	3140
shale blue	285	red rock	1833	lime K.C.	3148
shale & iron	287	lime	1868	shale and shells	3164
shale blue	305	shale	1873	red rock	3166
sand	310	lime	1897	lime	3168
slate blue	325	shale blue	1915	conglomerate	3214
hole caving.		lime	1985	Siliceous lime	3250
shale blue	332	slate blue	2012	Hole of water 3245-49	
shale grey	339	lime	2017		
red rock	356	slate blue	2021		
Hole caving:		lime broken	2035		
red rock	485	slate & shells	2045		
lime	535	hole caving.			
4 BWPHR 485-90		shale & shells	2050		
lime	562	lime	2055		
slate blue	565	slate blue	2075		
red rock	705	slate and shells	2110		
lime grey	710	hole caving.			
red rock	725	red rock	2115		
slate grey	740	shale blue	2127		
slate & shells	770	slate & shells	2145		
slate blue	780	slate blue	2207		
slate grey	790	caving 2155			
red rock	800	lime	2225		
shale blue	803	hole caving 2220			
lime grey	805	shale	2230		
red rock	829	slate	2274		
shale blue	905	lime broken	2278		
slate blue & shells	930	lime hard	2298		
shale blue	934	slate blue	2310		
shale salt	1219	lime	2325		
shale blue	1230	slate and shells	2340		
slate blue & shells	1260	2 BWPHR 2272-78			
lime	1270	lime	2355		
slate grey	1274	shale blue	2411		
lime	1280	lime white	2435		
lime broken	1300	slate blue	2446		
lime	1312	lime broken	2455		
slate brown	1325				

Total Depth.