

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. Center of SE $\frac{1}{4}$

Sec. 3 T. 14 R. 11W.


Casing Record.

County. Russell

10" 1965 Farm. Pasek
 20" 314'98 $\frac{1}{4}$ " 3085 Company. Deep Rock & Palmer.
 15 $\frac{1}{2}$ " 593'865/83395 Contr. Rosenthal & Beardmore.
 12 $\frac{1}{2}$ " 129453/16" Comm. 12-29-31
 Total Depth. 3427 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.

No. 1

Comp. 3-29-32



Elevation.

Initial Production. DRY

Figures Indicate Bottom of Formations.

Date Issued. 4-16-32

Formation	Depth	Formation	Depth
soil yellow soft	10	shale blue soft	2325
slate blue soft	150	lime white hard	2350
sdv shale blue soft	170	shale blue soft	2360
sand pink soft	190	sand white soft	1 $\frac{1}{2}$ BW 2370
sand white soft wtr	305	shale grey soft	2395
slate blue soft	315	lime white hard	2405
slate white soft	380	slate blk soft	2415
sand white soft wtr	390	lime white hard	2420
shale blue soft	450	slate blk soft	2425
sand white soft	475	lime white hard	2445
lime white soft	480	broken lime wh hard	2475
shale blue soft	495	slate blk soft	2520
lime white soft	500	lime white hard	2530
shale dark soft	515	shale grey soft	2550
red rock red soft	644	broken lime wh hard	2575
lime white hard	675	lime white hard	2690
red rock red soft	840	sand white soft	2695
shale blue soft	890	lime white hard	2705
red rock red soft	940	shale grey soft	2712
shale blue soft	955	lime white hard	2720
red rock red soft	965	shale grey soft	2730
shale blue soft	1040	lime white hard	2855
shale and salt soft	1294	shale blue soft Cave	2875
shale and shells soft	1335	lime white hard	2880
lime white hard	1400	shale blue soft	2885
shale blue soft	1420	lime white hard	2888
lime white hard	1430	red rock red soft	2893
shale blue soft	1440	shale blue soft	2915
red rock red soft	1445	sand white soft 4BW	2930
lime white hard	1500	shale and lime soft	2940
shale blue soft	1510	shale blue soft	2950
lime white soft	1545	lime white hard	2980
slate blue soft	1555	red rock red soft	2985
red rock red soft	1560	lime white hard	3030
lime white soft	1610	shale grey soft	3034
shale light soft	1615	broken lime wh med	3045
lime white soft	1705	lime white hard	3060
shale light soft	1715	sand white soft HFV	3070
lime white soft	1765	lime white hard	3155
shale dark soft	1770	shale blk soft	3158
lime white soft	1775	lime white hard	3168
red rock red soft	1800	shale grey soft	3177
lime white soft	1825	lime white hard	3200
red rock red soft	1830	shale blue soft	3210
lime white hard	1845	lime white hard	3225
red rock red soft	1850	shale grey soft	3235
lime white hard	1865	lime white hard	3245
shale light soft	1875	shale blue soft	3260
lime white soft	1900	conglomerate Various sft	3275
red rock red soft cave	1925	lime white hard	3280
lime white soft	1975	conglomerate various soft	3295
shale blue soft	2000	shale green soft	3300
lime white hard	2010	conglomerate various sft	3305
shale blue soft	2025	lime white hard	3310
shale and shells soft	2090	shale green soft	3315
shale blue soft	2125	S. lime wh hard	3320 HFV
lime white hard	2135	shale green soft	3330
shale blue soft	2180	S. lime wh hard	3348
lime and shale hard	2220	shale green soft	3353
red rock red soft	2230	lime white hard	3400
lime white hard	2245	shale green soft	3404
shale blue soft	2260	lime white hard	3427 T.D.
sand brown soft Gas.	2270		