

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location *Len 8/2*

29419

Sec. 25 T. 14 R. 11W.


Casing Record

20" 10" 1810
 15 1/2" 312 8 1/4" 2820
 12 1/2" 1162 65/8" 3332
 Total Depth 3503'
 53/16"

Farm- Stoppel
 Company- Douglas Oil Co.
 Contr.-
 Comm.- 4/16/1928. Comp.- 7/28/1928.
 Shot Quarts Between

County Russell.

No. 1



Correspondence Regarding This Well Should Be Referred to

Figures Indicate Bottom of Formations.
 Date Issued. 8/11/1928.

Ele ation
 Initial Production Dry.

Formation	Depth	Formation	Depth	Formation	Depth
sft drk soil	10	red shale	1600	white lime	2505
sft brown sand	30	white lime	1630	lime	2570
grey sand	40	black shale	1635	4 BW 2540-2560'	
blue slate	90	white lime	1645	light shale	2580
red shale	115	red rock	1665	white lime	2625
brown shale	125	white lime	1670	sft white lime	2730
light shale	140	light shale	1675	hrd blue shale	2740
sandy lime 14 BW	160	red shale	1680	white lime	2750
white shale	195	white lime	1690	white shale	2760
white sand HFW 220'	220	red shale	1710	red rock	2765
white lime	230	white lime	1730	white sandy	
dark shale	255	red shale	1740	lime 2 BW	2768
light sandy lime	260	white lime	1770	brown shale	2775
dark shale	300	red shale	1782	drk sand 8 BW	2780
light shale	314	white lime	1787	sandy shale	2785
15 1/2" 312'		red shale	1810	Cave 18 BW PH	
red shale	410	10" at 1810'		light lime	2820
red shale	460	white lime	1825	8 1/4" at 2820'	
white lime	500	light shale	1835	white lime shells	2830
red shale	525	white lime	1840	red rock	2835
red shale	690	blue shale	1850	lime	2840
light lime shells	715	red shale	1855	Cave 2830-2835'	
dark shale	725	blue shale	1865	white sdy lime	2965
red shale	765	white lime	1890	2 BW 2905-10'	
brown shale	875	dark shale	1895	dark shale	2970
light salt	1150	broken white lime	1905	Show oil 2955-57'	
dark shale	1162	white lime	1915	white lime	2992
12 1/2" at 1162'		dark shale	1950	dark shale	2995
light shell	1175	white lime	1960	white lime	3000
lime	1185	blue shale	1980	dark & light lime	
shale	1190	dark lime shells	1995	shells	3010
lime	1200	blue slate	2020	white lime	3072
white lime	1210	blue shale	2050	dark shale	3085
white shale	1215	white lime	2055	white lime	3105
white lime shells	1250	blue shale	2065	dark shale	3110
dark shale	1260	red shale	2085	white lime	3120
lime light	1285	hard lime	2095	red rock	3123
light shale	1290	sft slate	2175	dark shale	3140
red shale	1295	hrd lime	2185	lime shells white &	
white lime	1305	dark shale	2205	red	3195
white shale	1315	dark sand	2215	red rock	3197
white lime	1320	dark shale	2230	light lime	3200
black shale	1325	sft dark shale	2235	chatty white lime	
white lime	1330	hrd light lime	2255		3205
white sdy lime	1350	sft slate	2260	chatty white lime	
Show oil 1335'		hrd light lime	2270	caving	3255
white shale	1355	dark shale	2275	lime	3290
red rock	1370	light lime	2280	white sandy lime	
white lime	1405	dark shale	2290		3297
light shale	1410	white lime	2300	green shale	3300
red shale	1435	blue shale	2310	lime shells &	
white lime	1460	hrd lime	2330	green shale	3340
white shale	1465	dark shale	2335	2 BW PH 3320-3325'	
white lime	1505	white lime	2340	6" at 3332'	
light shale	1510	blue shale	2380	green shale	3345
white lime	1550	white lime	2390	sandy lime	3355
white sandy lime	1560	dark shale	2395	HFW 3345-50'	
brown shale	1565	white lime	2410	white sandy lime	
white lime	1570	light shale	2415		3365
red shale	1575	white lime (OVER)	2445	white sdy lime	3400
white lime	1595	blue shale	2455	HFW 3375-80'	