

PROPERTY MANAGEMENT  
LEASE OPERATIONS

A SERVICE OF THE OIL INDUSTRY

WELL COMPLETIONS  
RE-COMPLETIONS

C. E. (ED) LEITH  
OPERATIONS  
427 UNION CENTER BLDG.  
WICHITA, KANSAS 67202  
TELEPHONE 316-265-3491

DAVIES & COMPANY, INC.  
1304 Philtower Building  
Tulsa, Oklahoma 74103

MARY BAUMRUCKER NO. 1-8  
C NE NW Sec. 8-14S-11W  
Russell County, Kansas

CASING RECORD

December 6, 1978

Ran, set and cemented 60 jts. 2355' - 4½"OD 9.5# 8rd. R-3, Smls. Casing  
@ 2350' - cemented w/ 125 sacks Common cement 10% salt - 12½#/sack Gilsonite  
Good returns during cementing - Plug down @ 5:45 AM 12-6-78

Shoe joint 39' long - Float @ 2311'.

December 7, 1978

Ran temperature survey - found top cement 1720' and total depth 2292'.

MAR 04 1986

State Geological Survey  
WICHITA BRANCH

PROPERTY MANAGEMENT  
LEASE OPERATIONS

A SERVICE OF THE OIL INDUSTRY

WELL COMPLETIONS  
RE-COMPLETIONS

C. E. (ED) LEITH  
OPERATIONS  
427 UNION CENTER BLDG.  
WICHITA, KANSAS 67202  
TELEPHONE 316-265-3491

DAVIES & COMPANY, INC.  
1304 Philtower Building  
Tulsa, Oklahoma 74103

MARY BAUMRUCKER WELL NO. 1-8  
C NE NW Sec. 8-14S-11W  
Russell County, Kansas.

COMPLETION RECORD

SUMMARY:

Total Depth : 2350'

Plug Back Total Depth 2293'

Perforations: 2281'-2288', 2201'-2208' & 2180'-2184'.

Stimulation: 20,000# 20/40 sand + Foam Frac.

Tubing: 70 jts. 2180' - 2-3/8" EUE 8rd.

Seating Nipple: 2-3/8" x 12" Set @ 2181'.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 3 1986

CONSERVATION DIVISION  
Wichita, Kansas