

ROTARY DRILLING LOG

17-14-11W
SW NE 11W

JAN 16 1971

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 8/3/70

Rotary Drilling Completed 8/10/70

LOCATION:

Stoppel "A" No. 1, SW NE NW Section 17-14S-11W,
Russell County, Kansas

ELV. 1710' KB

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

Dry/air

CASING RECORD: Run 10 Jts. 8-5/8" surface casing set @ 205' K.B. Cemented with
130 sacks cement. Completed 6 P.M. Circulated.

No oil string run. D & A, Plugged 9:45 AM August 10, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		C.F.S.
40	Sandy Clay	
205	Shale & Sand Streaks	2200
550	Shale, Red Bed w/Sand Streaks	2500
578	Anhydrite	2698
645	Shale	2865
1250	Shale - Shells	2930
1930	Lime & Shale	3030
2200	Shale & Lime	3213
2400	Sand Shale & Lime	3228
2550	Shale - Lime	
3228	Lime, RTD	

Slope Tests

2000
2500
3000

Log Taps

Anhydrite	548
Fair Ls	2216
Howard	2413
Joplin	2452
Heebner	2728
Toronto	2748
Bn L	2817
Lansing	2830
Arbuckle	3205