


28-14-11W
NW SE NE

DRILLERS LOG

#1 Bunker



API # 15-167-20,548

CASING RECORD:

COMPANY: Kenneth Rupp

DESCRIPTION:

8 5/8" @ 208.05'
w/175 sk cement

CONTRACTOR: Red Tiger Drilling Co.

NW SE NE

COMMENCED: May 30, 1972

28-148-11W

COMPLETED: June 7, 1972

Russell, ~~County~~
Kansas

TOTAL DEPTH: 3200'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	35	
Shale, Clay & Strks of Hard Sand	35	203	
Shale w/streaky sand	203	350	
Red Bed & Shale	350	473	
Anhydrite	473	505	
Red Bed, Shale & Shells	505	800	
Shale, Shells & Salt	800	1175	
Shale	1175	1183	
Lime & Shale	1183	2100	
Sand	2100	2120	
Lime & Shale	2120	2445	
Lime	2445	2450	
Lime & Shale	2450	2660	
Lime	2660	2725	
Lime & Shale	2725	2832	
Lime	2832	3175	
Cherty Lime & Arbuckle	3175	3200	



I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 9th day of June, 1972.