

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

425699.pdf

Company- ALLAN ,ET AL
Farm- Bohnen

No. 1

SEC. 10 T. 14 R. 12W
SW SE SW

Total Depth. 3314'

Comm. 6-3-59

Comp. 6-14-59


Shot or Treated.

Contractor. Thos. H. Allan

Issued. 8-1-59

County Russell

KANSAS



Elevation. 1812' RB

CASING:

8 5/8" 470' cem w/175 sx.

Production. Dry

All depths from RB.

Figures Indicate Bottom of Formations.

soil	15
lime rock	50
blue shale	160
gray shale & sandstone	225
red & gray shale	360
sandy shale	446
sandstone	450
red beds	470
red shale	690
Anhydrite	726
red shale	950
shale	1050
salt & shale	1300
shale & Anhydrite	1500
lime & shale strks	1800
shale & shells	2550
lime	2800
porous lime	2820
lime	2845
black shale	2848
hard buff lime	2852
shale	2863
white lime, little	
oil saturation	2879
shale	2890
sandstone & grit	2901
shale	2923
lime	2936
oolicastic lime	2940
lime	2960
oolicastic lime	2978
lime	3014
shale	3019
cherty lime	3025
soft oolicastic lime	3040
show of oil in top	
hard lime	3045
oolicastic lime	3050
lime	3065
shale	3070
lime	3111
soft porous lime	3126
hard lime	3145
soft shale & lime	3158
lime	3190
cherty lime	3193
lime	3210
red & gray shale	3247
lime	3250
shale	3268
varicolor cherts in	
red mud	3290
red & green shale	3293
dolomite & chert	3314
Total Depth	

TOPS:

Anhydrite	690
Heebner	2845
Toronto (scout)	2863
Lansing	2928
Sooy Conglomerate	3268
Arbuckle	3293

DST 2865-2931', gas in 30 min., 50' rotary mud,
BHP 1010#.