


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHELLEY-MILLER DRG., INC.
Farm- Teppe "B" No. 1

SEC. 21 T. 14 R. 12W
SE SE NE

Total Depth. 3285'
Comm. 5-28-54 Comp. 6-6-54
Shot or Treated.
Contractor. Shelley-Miller Drlg., Inc.
Issued. 7-31-54

County Russell
KANSAS



CASING:
8 5/8" 183' w/140 sx cem.
5 1/2" 3285' w/75 sx cem.

Elevation. 1741'

Production. 96 bbls./no wtr.

Figures Indicate Bottom of Formations.

Meas. from top R.B. to bottom.
red bed-shale 610
red bed 646
anhydrite 685
shale-shells 1270
lime 1460
lime-shale 2605
lime 3285 RTD.
Total Depth

TOPS:
Tarkio 2249
Topeka 2779
Heebner 2816
Toronto 2834
Lansing 2901
Conglomerate 3224
Gorham 3233

DST #1 3224-3247, open
1 hr., Good blow thruout.
Rec. 670' muddy oil.
SIP., 20 min., 665#
Final flowing pressure
230#.

DST #2 3248-3261, open
10 min. Rec. 8' mud.
No S.I.P. taken.