

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY FRED J. HAYNES

SEC. 28 T. 14 R. 12W
LOC. NW NW SE

FARM Grove

NO. 1

TOTAL DEPTH 3184

COMM. 1-2-51

COMP. 2-14-51


SHOT OR TREATED

CONTRACTOR

ISSUED 4-14-51

COUNTY Russell

KANSAS



CASING

15" 20' 7" 2875'
12" 328' 5" 3095'
10" 590'
8" 1955' UR 2242

ELEVATION 1692

PRODUCTION Dry

	10	FIGURES INDICATE BOTTOM OF FORMATIONS
cellar	10	
shale blue & red	150	
sand	170	
shale	290	
sand	300	
red rock	590	
lime	622	
red rock	800	
shale	985	
salt	1220	
shale & shells	2290	
sand, lime, & shale	2330	
shale	2500	
lime	2785	
shells	2810	
lime	2818	
shale, blue	2825	
shale red	2835	
shale blue	2868	
lime	3095	
shale	3155	
congl.	3170	
lime	3180	
sand	3184	
Total Depth		
Tops		
Anhyd.	590	
Kansas City	2875	
Sand	3180	

Water:

HFW	170
Wtr.	290
2 BW	370
2 BW	1895
1/2 BW	2905
HFW	3090
HFW	3180

No Oil shows