


CITIES SERVICE OIL CO.
Marsh "C" No. 1.

SEC. 29 T. 14 R. 12 W
CS $\frac{1}{2}$ SW SW
330' N 660' E SW Cor.

County. Russell



Total Depth. 3166-3164 SIM
Comm. 7-8-43 Comp. 7-18-43
Shot or Treated. None
Contractor. Corbett-Barbour Drlg. Co.
Issued. 9-25-43

CASING:
8 5/8" 314' Cem.
5 1/2" 3162' Cem.

Elevation.

Production. Phy. Pot. 238 B.
no wtr

Figures Indicate Bottom of Formations.

surface	0-40
sand & red bed	195
clay & shells	314
shale	350
red bed	665
anhydrite	695
sand, shale, red bed	1120
shale	1320
lime, shale, sand	1440
shale, shells, sand	1675
lime, shale, sand	1965
lime & shale	2130
shale	2495
shale & shells	2595
lime & shale	2695
lime	3164
sand	3166

3166 Rot. TD=3164 SIM
Total Depth.

Corr. Top Gorham 3162
Penetration 2

Fillup: 250' oil in 1 hr
375' oil in 1 $\frac{1}{2}$ hrs
1300' oil in 4 hrs
1700' oil in 6 hrs
2000' oil in 8 hrs
2500' oil in 12 hrs

7-28-43 Temporary physical
potential 164 oil, no wtr
24 hrs