


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO.
Marsh "B" No. 1.

SEC. 30 T. 14 R. 12 W
CSL SW SE
330' N 660' E S $\frac{1}{4}$ Cor.

Total Depth. 3096'
Comm. 4-17-43 Comp. 5-4-43
Shot or Treated. None
Contractor. Corbett-Barbour Drlg. Co.
Issued. 7-3-43

County. Russell



CASING:
12 $\frac{1}{2}$ " 39' Cem.
8 $\frac{5}{8}$ " 318' Cem.
5 $\frac{1}{2}$ " 3093' Cem.

Elevation.

Production. Echo. Pot. 2669 B.

Figures Indicate Bottom of Formations.

No Wtr

sand	0-20
shale	39
red bed & shale	100
shale & shells	200
sand & gravel	220
lime & shale	318
red bed & shale	535
red rock & shells	925
shale & shells	1070
salt	1210
shale & lime	1320
lime & shale	1460
shale & lime	1590
lime	1690
lime sdy	1710
lime	1775
lime & shale	2005
shale & shells	2140
shale & lime shls	2310
shale & lime	2430
lime	2740
shale & lime	2815
lime	3096
3096 Rot. TD=3094 SIM	
sand	3096
Total Depth.	

Corr. Top Gorham 3093
Penetration 3

Fillup:
675' oil in 30 min.
2150' oil in 55 min.
2450' oil in 1 hr, 25 min.
2800' oil in 3 hrs

5-10-43 Temp. Pot. 92 oil,
no wtr