


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- J. M. Trapp No. 9

SEC. 31 T. 14 R. 12W
NW SW NE

Total Depth. 3207 PB 3180
Comm. 10-24-53 Comp. 11-17-53
Shot or Treated.
Contractor. Barnett Drilling Co.
Issued. 2-13-54

County Russell
KANSAS



CASING:
9 5/8" 398' cem. w/250 sx.
6 5/8" 3206' cem. w/175 sx.

Elevation. 1679' DF

Production. P 35 BO & 260 BW in
24 hrs.

Figures indicate Bottom of Formations.

surface clay	20
rock & shale	65
shale	80
sand	100
shale	260
sand	285
shale & shells	395
red bed, shale & shells	618
anhydrite & lime	647
shale & shells	885
shale	1245
shale & shells	1475
lime & shale	1690
lime	1756
shale & lime	2684
lime	2735
lime & shale	2825
lime	3207
Total Depth PB 3180	

TOPS:
Grandhaven Lime 2165
Tarkio Lime 2239
Heebner 2746
Lansing-Kansas City 2826
Gorham Sand 3112
Arbuckle 3129
Reagan Sand 3176

D.S.T. 2864-70, open 1 hr.,
SI 20 min., good blow,
rec. 450' gas, 50' oil &
gas cut mud, 20' hvy oil
& gas cut mud, BHP 440#,
building.

D.S.T. 3135-40, open 1 hr.,
SI 20 min., rec. 120' mud-
dy wtr, 240' sl. oil specked
wtr. BHP 1035#.

Perf. 3111-14 w/12 shots,
swb. 5 BO, 7 BHPH, 2000'
off bottom, 8 hrs.