


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

SKELLY OIL CO.
C. Pekarek No. 1.

SEC. 31 T. 14 R. 12 W
CS1 NE SE
990'f NL 660'f EL SE $\frac{1}{4}$

Total Depth. 3186'SIM
Comm. 6-27-43 Comp. 7-15-43
Shot or Treated. 500 Acid
Contractor. C. Wentworth
Issued. 9-25-43

County. Russell



CASING:
10 3/4" 686' Cem.
6" 3184' Cem.

Elevation.

Production. Pot. 1462 B.

Figures Indicate Bottom of Formations.

soil, clay, gravel, sand	170	While cleaning out on
shale, sand, iron, shells	280	btm hole filled 350'
red rock & shells	375	w/oil in 30 min.
shale & shells	610	700' in 1 hr
red rock & shells	685	1200' in 2 hrs
anhydrite	715	2100' in 4 hrs
shale & shells	1460	2400' in 6 hrs
sdv lime	1550	
shale & lime	1600	
lime	1625	
shale & lime	1705	
sand & lime	1765	
lime & shale brks	1830	
lime & shale	1895	
lime	1933	
shale & shells	2010	
shale	2040	
lime	2075	
shale	2089	
shale & sand	2110	
lime	2138	
lime & shale	2220	
shale & shells	2316	
lime brkn	2396	
sdv lime	2435	
shale, lime shells	2560	
lime brkn	2635	
lime	2665	
lime & shale	2715	
lime	2730	
shale & lime shells	2755	
lime	2779	
lime & shale	2902	
lime shells & shale	2920	
lime	2953	
lime & shale	3003	
sand & shale	3014	
lime	3031	
shale & lime shells	3103	
lime brkn & shells	3138	
lime	3175	
shale red & gy & chert	3185	
dolomite gy & brown		
coarsely xlyn, porous,		
slight saturation	3187	
3187 equals 3186 SIM		

Total Depth.

Tops: Lansing 2893
Lansing pay 2909-15
and 2926-37
Arbuckle 3184 SIM