


Company - JONES-SHELBURNE, INC.
 Farm - Kaps No. 1.

SEC. 32 T. 14 R. 12 W
 CSE SW

Total Depth. 3208
 Comm. 10-24-44 Comp. 12-3-44
 Shot or Treated.
 Contractor.
 Issued. 1-13-45

County. Russell
 KANSAS



CASING:
 15 1/2" 380'
 12 1/2" 685'
 10" 1956'

8 1/4" 2380'
 7" 3103'
 5 1/2" 3206'

Elevation. _____

Production. Pot 172 BO

Figures Indicate Bottom of Formations.

surface formations & cellar		shale & shells	2360
sandy shale	0-15	shale	2370
sandy shale	50	lime	2385
shale	120	shale	2400
sandy shale	150	lime	2435
shale	215	shale	2447
sand	240	lime	2465
shale	290	shale	2477
sand	300	lime	2480
shale	320	shale	2515
shale sdy	340	lime	2520
shale	360	shale	2525
sand	370	lime	2535
shale	380	shale	2547
red rock	678	lime	2577
lime (anhydrite)	710	shale	2587
red rock	885	lime	2605
shale	930	shale	2610
red rock	990	lime	2635
shale	1100	shale	2642
salt	1330	lime	2690
shale & shells	1349	shale	2695
lime & shale brks	1415	lime (1 1/2 BW 2800)	2825
shale	1420	shale blk	2828
lime	1440	lime	2830
shale	1443	shale	2842
lime	1455	lime	2860
red rock	1460	red rock	2865
lime	1515	shale	2908
shale	1520	lime	2915
lime	1550	shale	2923
shale & shells	1585	lime	2940
lime	1700	shale	2945
lime & shale brks	1740	lime	2960
shale	1745	shale	2965
lime	1770	lime	2987
shale & shells	1810	shale	2989
lime	1815	lime (show Oil 3002-10)	3025
red rock	1822	lime-shale brks	3050
lime & shale brks	1890	lime (wtr 3096-3103)	3120
lime	1920	shale	3125
red rock	1943	lime	3175
lime (wtr 1943-55)	1956	shale	3180
shale brks & lime	2040	lime	3187
lime	2050	shale	3190
shale	2060	lime (show Oil 3203-06)	3206
lime	2105	lime OIL	3208
shale	2125	Total Depth	
lime	2140		
shale	2145		
lime	2155		
shale & shells	2178		
lime	2184		
shale	2195		
lime	2200		
lime shells & shale	2270		
shale	2314		
lime	2330		
shale	2335		