

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - JONES-SHELBURNE, INC.
Farm - Kaps No. 3

SEC. 32 T. 14 R. 12 W
SWc SW

Total Depth. 3261' PB 3070'
Comm. 7-17-45 Comp. 9-10-45
Shot or Treated.
Contractor.
Issued. 11-10-45

County. Russell
KANSAS



Elevation. _____

Production. Pot. 263 B.

CASING:
15 1/2" 410' 8 1/4" 2380'
12 1/2" 722' 7" 2987'
10" 2004' 5 1/2" 3261'

Figures Indicate Bottom of Formations.

surface formation	shale	2030	show oil & little
& cellar	0-20 lime	2050	wtr. 2965-70'
yellow clay	30 shale	2060	sft lime -show oil
shale	140 red rock	2065	2974-87'
red rock	175 lime	2090	shale 2974
some wtr 180'	shale	2100	lime 3030
shale	200 lime	2140	sft lime-3020-28'
red rock	275 shale	2160	hole filling w/oil
shale	320 lime	2175	lime 3050
4 BW 280'	lime & shale	2185	sft lime & oil
sand	325 shale & shells	2200	3037-43'
shale sdy	330 lime	2210	lime 3115
sand	338 shale	2215	little wtr 3092-97'
shale	413 lime	2220	shale 3118
red rock	717 shale	2230	lime 3155
lime-anhydrite	755 lime	2240	shale 3158
shale	760 lime & shale	2270	lime 3162
red rock	830 shale	2275	shale 3167
shale	890 lime	2290	lime 3172
red rock	920 shale	2355	show oil 3172-74'
shale	970 lime	2360	lime sft 3174
red rock	1025 shale	2365	lime 3195
shale	1140 lime	2380	shale 3202
salt	1370 shale	2410	lime & shells 3203
shale	1380 lime	2420	shale 3205
shale & shells	1445 shale & shells	2430	lime 3219
lime	1460 lime	2445	shale 3222
red rock	1475 shale	2460	lime 3244
lime	1485 lime	2465	shale 3248
shale	1495 shale	2470	lime 3261
lime	1500 lime	2480	Total Depth. PB 3070'
red rock	1505 shale	2485	
shale & shells	1520 lime	2495	Sft lime 3260-61'
lime	1545 shale	2515	HFW 3261'
shale	1565 lime	2520	Plugged back to 3070'
lime	1600 shale	2525	
shale	1610 shale & shells	2575	
red rock	1630 shale	2580	
lime	1660 lime	2590	
1/2 BW 1650-60'	shale	2593	
shale	1670 shale	2610	
lime	1765 lime	2617	
red rock	1775 shale	2640	
lime	1800 lime	2645	
shale	1805 shale	2710	
lime	1840 lime	2713	
shale	1855 shale	2720	
lime	1875 lime	2726	
red rock	1880 1/2 BW 2742-46'	2885	
lime	1890 show oil 2790-2800'		
red rock	1895 1 BWPH 2825-35'		
lime	1915 redrock	2890	
shale	1920 shale	2900	
lime	1930 red rock	2930	
shale	1937 shale	2944	
lime	1965 lime	2952	
red rock	1985 shale	2959	
lime	2020 lime	2970	
show wtr 1985-2000'			