

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


TEXAS COMPANY
E. A. Borell No. 1.

SEC. 32 T. 14 R. 12W.
CN $\frac{1}{2}$ NE SE

County Russell.

Total Depth. 3170'
Comm. 3-25-41 Comp. 4-2-41
Shot or treated. 1000 gal acid.
Contractor. Helmerich and Payne, Inc.
Issued. 5-31-41

Rotary 2880
Cable 3170



CASING.

103/4" 362' cemented.
7" 2880' cemented.
348'6" of 5 1/2" liner set 3165'

Elevation.

Production. Pot. 464 B.
Physical No wtr.

Figures Indicate Bottom of Formations.

surface loam	25
sand	35
red bed and sand rock	80
sand	220
shale and shells	362
red bed and shale	650
anhydrite	675
red bed and shale	855
red bed and shells	1115
salt and shale	1326
anhydrite and shale	1412
shale and sand	1544
shale and shells	1560
lime shale and pyrite	1705
sdv lime and pyrite	1786
broken lime and sand	1925
broken lime	2225
broken lime and shale	2354
broken lime	2442
lime and shale	2539
lime and chert	2657
lime	2798
lime shale and sand	2863
K.C. lime	2870
lime	2934
shale	2937
lime hard	2947
broken lime	2962
lime soft	2982
lime	3006
lime hard	3018
lime	3052
broken lime	3060
lime	3088
shale and shells	3098
broken lime	3111
lime hard	3114
lime	3137
broken lime	3142
shale	3146
lime hard	3148
broken lime and shale	3157
shale	3163
lime	3170
Total Depth.	