


CITIES SERVICE OIL CO.
Kejr No. 2.

SEC. 33 T. 14 R. 12 W
CS $\frac{1}{2}$ SW SE
330' N 660' E S $\frac{1}{4}$ Cor.

County. Russell

Total Depth. 3240'
Comm. 6-25-43 Comp. 7-12-43
Shot or Treated. None
Contractor. Veeder Sup&Dev Co.
Issued. 8-21-43



CASING:
8 5/8" 317' Cen.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

clay & sand	0-35
shale & lime	190
iron pyrite	198
shale & lime	317
shale & red rock	590
red bed	612
anhydrite	650
shale & shells	1005
shale, shells, red bed	1250
shale & salt shells	1320
lime	1365
shale & lime	1385
shale	1390
lime	1430
lime brkn	1470
anhydrite	1515
iron pyrite & sdy lime	1553
lime	1640
shale	1670
lime	1690
shale	1705
lime	1760
lime & shale	1775
shale	1890
lime	1915
shale & lime	2040
shale	2070
sdv lime	2090
lime brkn	2100
shale & shells	2305
shale & lime	2395
shale & shells	2470
shale	2505
lime brkn	2550
shale & shells	2610
lime	2643
shale	2660
lime brkn	2760
lime & shale	2960
lime	3055
lime brkn	3100
lime	3180
lime & sand	3195
sand	3199
lime & chert	3214
sand	3240
Total Depth.	

Tops: Lansing	2899
Conglomerate	3193
Reagan	3210

No shows