


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JONES-SHELBURNE, INC.
Farm- Marsh "C" No. 1

SEC. 29 T. 14 R. 12W
SW SE SW

Total Depth. 3140'
Comm. 3-23-54 Comp. 4-30-54
Shot or Treated.
Contractor.
Issued. 7-10-54

County Russell
KANSAS



Elevation. 1686' DE

CASING:
8" 2275'
5 1/2" 3139' cem w-150 sx

Production. 30 bbls & no wtr.

Figures Indicate Bottom of Formations

cellar	10	lime	2155
sand	18	shale	2170
shale	75	red rock	2175
sand	130	lime	2199
shale red	135	sandy shale	2210
shale	190	lime	2213
shale grey	205	shale	2260
blue shale	220	lime	2280
shale	344	shale	2315
red rock	632	lime	2340
anhydrite lime	639	shale	2345
lime	668	lime	2350
red rock	845	shale	2360
shale blue	890	lime	2395
red rock	940	shale	2405
shale	1025	lime	2410
blue	1060	shale	2445
salt	1105	lime soft	2465
shale	1115	shale	2470
salt	1285	lime	2510
blue shale	1320	shale	2516
lime	1330	lime	2760
shale & shells	1340	shale	2770
lime	1360	dodge lime	2785
shale	1365	shale red	2795
lime	1395	shale	2837
red rock	1400	lime Lansing	2850
lime	1425	shale	2855
blue shale	1430	lime	3055
lime	1455	shale	3058
red rock	1465	lime	3080
lime	1500	shale	3085
shale	1510	lime	3116
red rock	1530	red	3120
lime	1650	lime, shell & shale	3128
sharp	1662	lime	3140
blue	1665	Total Depth	
red rock	1670		
lime	1730	Tops: Scout	
shale	1750	Tarkio	2222
lime	1800	Arbuckle	3139
red rock	1810		
lime	1825	Oil or Gas Sands or Zones	
blue shale	1830	Kansas City	2837-2850
red rock	1835	Arbuckle	3139
lime	1860		
red rock	1880	Perforating Kansas City	3859-66 w/21 shots.
lime	1893		
water sand	1900		
lime	1920		
shale	1923		
lime	1957		
red rock	1968		
lime	2050		
blue shale	2060		
lime	2075		
shale	2100		
lime	2110		
shale	2135		