

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISIONWELL COMPLETION OR RECOMPLETION FORM
ACO-1 WELL HISTORY

DESCRIPTION OF WELL AND LEASE

Operator: license # 6598
 name MVRC Oil Operations
 address 132 Cindy Drive
 Russell, KS 67665
 City/State/Zip

Operator Contact Person Marvin E. Mader
 Phone 913 483 2911

Contractor: license # 5652
 name Mustang Drilling & Exploration, Inc.

Wellsite Geologist Brad Hutchinson
 Phone 913 483 6637

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover

☐ Oil ☐ SWD ☐ Temp Abd
☐ Gas ☐ Inj ☐ Delayed Comp.
☒ Dry ☐ Other (Core, Water Supply etc.)

If OWWO: old well info as follows:

Operator
 Well Name
 Comp. Date Old Total Depth

WELL HISTORY

Drilling Method: ☒ Mud Rotary ☐ Air Rotary ☐ Cable
 7-28-84 8-2-84 8-2-84
 Spud Date Date Reached TD Completion Date

5320'
 Total Depth PBTD

Amount of Surface Pipe Set and Cemented at 489' feet

Multiple Stage Cementing Collar Used? ☐ Yes ☐ No

If Yes, Show Depth Set feet

If alternate 2 completion, cement circulated
 from feet depth to w/ SX cmt

API NO. 15 - 167-22,427

County Russell
 150' W
 C. NE NE SE Sec 6 Twp 14s Rge 12w East
 (location) West

..... Ft North from Southeast Corner of Section
 Ft West from Southeast Corner of Section
 (Note: locate well in section plat below)


Lease Name ANCHUTZ Well# 1

Field Name Bunker Hill Ext

Producing Formation

Elevation: Ground 1817' KB 1822'

Section Plat



WATER SUPPLY INFORMATION

Source of Water:

Division of Water Resources Permit #

☐ Groundwater. Ft North From Southeast Corner and
 (Well) Ft. West From Southeast Corner of
 Sec Twp Rge ☐ East ☐ West

☐ Surface Water. Ft North From Southeast Corner and
 (Stream, Pond etc.) Ft West From Southeast Corner
 Sec Twp Rge ☐ East ☐ West

☒ Other (explain) purchased from farmers pond
 (purchased from city, R.W.D.#)

Disposition of Produced Water: ☐ Disposal
☐ Repressuring

Docket #

INSTRUCTIONS: This form shall be completed in duplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 90 days after completion or recompletion of any well. Rules 82-3-130 and 82-3-107 apply.

Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months.

One copy of all wireline logs and drillers time log shall be attached with this form. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

Operator Name MVRC Oil Operations Lease Name Anchutz Well# 1 SEC 6 TWP 14s RGE 12w ☐ East ☒ West

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken

☒ Yes☐ No

Samples Sent to Geological Survey

☐ Yes☒ No

Cores Taken

☐ Yes☒ No

Sand, Shale	0	493
Shale, Lime	493	2746
Lime, Shale	2746	2970
Shale, Lime	2970	3025
Lime, Shale	3025	3311
Shale, Lime	3311	3320
RTD		3320

Formation Description

☐ Log☐ Sample

Name

Top

Bottom

Anhydrite	745	
Topeka	2669	
Heebner	2903	
Douglas	2938	
Kansing	2974	
Conglomerate	3306	
RTD	3320	

DST #1 2983-3025 30/30 / 30/30

ISIP 530 Psi FSIP 308 Psi

FFP 86-57 psi HSH 1517-1441 psi

Rec. 10' of drilling mud

Weak blow, 7 minutes

IFP 77-57 psi

OCT 12 1984

State Geological Survey

WICHITA, KS 67201

CASING RECORD

☐ new☐ used

Report all strings set - conductor, surface, intermediate, production, etc.

Purpose of string	size hole drilled	size casing set (In O.D.)	weight lbs/ft.	setting depth	type of cement	# sacks used	type and percent additives
...Surface.....	..12 1/4".....	..8.578".....	..24#.....	..489'.....	60/40 poz	..225.....	3%cc. 2%gel.....
.....							
.....							
.....							

PERFORATION RECORD

shots per foot specify footage of each interval perforated

Acid, Fracture, Shot, Cement Squeeze Record

(amount and kind of material used)

Depth

.....			
.....			
.....			
.....			