


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SHELLEY-MILLER DRILLING, INC.  
Farm- Beisel No. 2

SEC. 15 T. 14 R. 12W  
NW SE SE

Total Depth. 3246'  
Comm. 10-26-62 Comp. 11-3-62  
Shot or Treated.  
Contractor.  
Issued. 2-2-63

County Russell  
KANSAS



CASING:  
8 5/8" 218' cem w/140 sx.  
4 1/2" 3237' cem w/100 sx.

Elevation. 1770' DE

Production. 25 BOPD

Figures Indicate Bottom of Formations.

(Meas. from top of RB)

|                       |          |
|-----------------------|----------|
| shale & shells        | 315      |
| shale & red bed       | 638      |
| anhydrite             | 670      |
| red bed & shale       | 850      |
| shale & red bed       | 935      |
| shell & shale         | 1250     |
| shale & lime          | 1375     |
| shale & shells        | 1690     |
| shells - shale & lime | 1835     |
| lime                  | 1953     |
| lime broken           | 2190     |
| lime broken - shale   | 2480     |
| shale & lime          | 2622     |
| lime                  | 2806     |
| shale                 | 2808     |
| lime & shale          | 2891     |
| lime                  | 2905     |
| Kansas City lime      | 2944     |
| lime                  | 3123     |
| lime & shale          | 3168     |
| lime & conglomerate   | 3233     |
| lime arbuckle         | 3237 RTD |
| lime arbuckle ?       | 3246     |
| Total Depth           |          |

TOPS: LOG

|                  |      |
|------------------|------|
| Tarkio           | 2212 |
| Heebner          | 2804 |
| Toronto          | 2824 |
| Douglas          | 2839 |
| Base Kansas City | 3176 |
| Conglomerate     | 3214 |
| Arbuckle         | 3235 |