

TYPE

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

✓ Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5184 EXPIRATION DATE 6-30-83

OPERATOR Shields Oil Producers, Inc. API NO. 15,167-21,915

ADDRESS Shields Bldg. COUNTY Russell

Russell, Kansas 67665 FIELD Beisel

** CONTACT PERSON M. L. Ratts PROD. FORMATION Kansas City
PHONE 913-483-3141

PURCHASER Mobil Oil Corp. LEASE Beisel "A"

ADDRESS P.O. Box 900 WELL NO. #2

Dallas, Texas 75221 WELL LOCATION SE SE NW

DRILLING Shields Drilling Co., Inc. 330 Ft. from East Line and

CONTRACTOR Shields Bldg. 330 Ft. from South Line of

ADDRESS Russell, Kansas 67665 the NW (Qtr.) SEC15 TWP 14 RGE 12W

PLUGGING
CONTRACTOR *Shields Drilling Co., Inc.*
ADDRESS *WICHITA, KS*

WELL PLAT			
	X	15	

TOTAL DEPTH 3288 PBTD 3027

SPUD DATE 5-18-82 DATE COMPLETED 7-26-82

ELEV: GR 1786 DF 1788 KB 1791

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING
USED TO DISPOSE OF WATER FROM THIS LEASE 86,468C

Amount of surface pipe set and cemented 245 DV Tool Used? No.

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

M. L. Ratts, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

M. L. Ratts
(Name)

W.S.1 - H1 - 21

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Shields Oil Producers, Inc. LEASE Beisel "A"SEC. 15 TWP. 14 RGE. 12 W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
D.S.T. #1 2238'-2280' 30-30-30-30 Rec. 30' Mud I.F.P. -51# I.S.I.P. -61# F.F.P. -51# F.S.I.P. -61#			Anhydrite Grandhaven Lm Tarkio Lm Topeka Lm Heebner Sh Toronto Lm L-KC Lm Conglomerate Reworked Arb	660 2232 2308 2582 2823 2842 2906 3246 3274
D.S.T. #2 2955'-3025' 30-30-30-30 Rec. 180' Gas 120' GCM 180' GOCM 120' HO&GCM 300' MGO I.F.P. -135# I.S.I.P. -837# F.F.P. -358# F.S.I.P. -827#				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated				
500 gal 15% & 2,000 gal 28%	2983-3004				
Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
7-26-82	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 25 bbls.	Gas Show MCF	Water 65 %	40 bbls.	Gas-oil ratio CFP
Disposition of gas (vented, used on lease or sold)	Perforations 2983-3004				

Report of all strings set—surface, intermediate, production, etc. Casing Record (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
						.	
Surface (New)	12 1/4	8 5/8	20	245	Quickset	160	
Production (New)	8 5/8	4 1/2	9 1/2	3053	Common	100	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None					
TUBING RECORD			2	1/2 Jet	2996-3004
Size 2" EUE	Setting depth 3025	Packer set at None	2	1/2 Jet	2983-2986