

State Geological Survey
WICHITA BRANCH

PT 15-14-1205

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

DOCKET NO. NP _____

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F _____ Letter requesting confidentiality attached.

C _____ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run X.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 6588

EXPIRATION DATE _____

OPERATOR Woodman & Iannitti Oil Company

API NO. 15-167-22,206

ADDRESS 1022 Union Center

COUNTY Russell

Wichita, Kansas 67202

FIELD Beisel

** CONTACT PERSON K.T. Woodman

PROD. FORMATION _____

PHONE (316)-265-7650

Indicate if new pay.

PURCHASER N/A

LEASE Beisel

ADDRESS _____

WELL NO. 8

DRILLING Woodman & Iannitti Drilling Company

WELL LOCATION SW NE SE

CONTRACTOR _____

990 Ft. from North Line and

ADDRESS 1022 Union Center

990 Ft. from East Line of (EX)
the SE (Qtr.) SEC 15 TWP 14 SRGE 12 (W).

Wichita, Kansas 67202

PLUGGING _____

WELL PLAT

CONTRACTOR _____

(Office Use Only)

ADDRESS _____

KCC

TOTAL DEPTH 3470' PDTD _____

KGS

SPUD DATE 9-24-83 DATE COMPLETED 10-7-83

SWD/REP PLG.

ELEV: GR 1771 DF -- KB 1776

NGPA

DRILLED WITH (XXXX) (ROTARY) (XX) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING
USED TO DISPOSE OF WATER FROM THIS LEASE N/A

Amount of surface pipe set and cemented 653' DV Tool Used?

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

AFFIDAVIT

K.T. Woodman

, being of lawful age, hereby certifies

that:

I am the Affiant and I am familiar with the requirements of the

(W51-41-21)

ACO-1 Well History

XX

Side TWO
OPERATOR Woodman & Iannitti Oil Co. LEASE NAME Beisel
WELL NO 8

SEC 15 TWP 14S RGE 12 (W)

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.			Topeka	2572 (- 796)
<input checked="" type="checkbox"/> Check if samples sent Geological Survey.			Heebner	2817 (-1041)
Shale	0	50	Toronto	2837 (-1061)
Surface Soil & Shale	50	130	Douglas	2850 (-1074)
Shale	130	225	Lansing-K.C.	2902 (-1126)
Sand	225	256	Base K.C.	3171 (-1395)
Red Bed	256	650	Conglomerate	3228 (-145)
Anhydrite	650	663	Arbuckle	3271 (-1495)
Anhydrite	663	676	Total Depth	3470 (-1694)
Shale	676	1175		
Shale	1175	1760		
Shale	1760	2120		
Shale	2120	2410		
Lime & Shale	2410	2616		
Shale & Lime	2616	2759		
Lime & Shale	2759	2960		
Lime & Shale	2960	3087		
Lime & Shale	3087	3210		
Lime	3210	3295		
Lime-Arbuckle	3295	3470		

If additional space is needed use Page 2

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or XXXXXX

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	660'	Common	300	3% CC, 2% Gel
Production	7-7/8"	5-1/2"	14#	3363'	50/50 Poz-mix -- Common --	50 50	2% Gel 15 Bbl. Salt Flush, 10% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at		