

22-14-12W
Ind

DRILLERS' WELL LOG X

DATE COMMENCED: February 18, 1976
DATE COMPLETED: February 25, 1976

Icer Addis
MILLER # 11
100' No. of SW NE NE
Sec 22-T14-R12
Russell County, Kansas

ELEVATION: 1741 K.B.

0 - 115'	Surface Soil, Clay, Shale, Post Rock
115 - 225'	Surface Clay, Sand
225 - 375'	Sand
375 - 608'	Red Bed
608 - 641'	Anhydrite
641 - 650'	Shale, Red Bed
650 - 1280'	Red Bed
1280 - 2532'	Lime and Shale
2532 - 2773'	Lime
2773 - 2777'	Shale
2777 - 2792'	Lime and Shale
2792 - 2806'	Lime
2806 - 2858'	Shale
2858 - 2871'	Lime and Shale
2871 - 3128'	Lime
3128 - 3146'	Lime, Shale
3146 - 3230'	Lime, Shale, Sand, Chert
3230 - 3300'	Dolomite
3300'	RTD

FORMATION TOPS	
Anhydrite	608
Topeka	2532
Heebner	2773
Toronto	2792
Douglas	2806
Brown Lime	2858
Kansas City	2871
Base K.C.	3128
Cong.	3146
Arbuckle	3230
RTD	3300

SURFACE PIPE:
Set 614' of used 8 5/8", 28#
pipe w/250 sacks 50/50 Pozmix,
2% Gel, 3% cc.

PRODUCTION PIPE:
Ran new 10 1/2", 4 1/2" casing @ 3272'
w/125 sacks 60/40 Pozmix, 18%
salt w/15 bbl salt flush ahead
of cement.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 26th day of February, 1976.

Deborah M. Nague
Notary Public