

**KANSAS DRILLERS LOG**

State Geological Survey  
WICHITA, BRANCH

API No. 15 — 167 — 20,830  
County Number

S. 22 T. 14S R. 12 W

Loc. SE SW NE

Operator


ICER ADDIS

County RUSSELL

640 Acres  
N

Address

Drawer 8038, Wichita, Kansas 67208



Locate well correctly

Elev.: Gr. 1,734'

Well No.

10

Lease Name

MILLER

DF 1,736' KB 1,739'

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Duke Drilling Company

Geologist

Richard M. Foley

Spud Date

February 10, 1976

Total Depth

3,225'

P.B.T.D.

Date Completed

February 16, 1976

Oil Purchaser

(Dry Hole)

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	28#	618	50-50 Pozmix Common	200 100	2% Gel, 3% CaCh 2% Gel, 3% CaCh

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production	(Dry Hole)					Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio		
	bbls.	MCF	bbls.	CFPB		
Disposition of gas (vented, used on lease or sold)					Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ICER ADDIS		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 10	Lease Name MILLER	DRY HOLE
S <u>22</u> T <u>14</u> R <u>12</u> <u>W</u>		

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	609			
Topeka	2,496			
Heebner	2,773			
Toronto	2,794			
Douglas	2,807			
Brown Lime	2,860			
Lansing	2,870			
Base Kansas City	3,133			
Conglomerate	3,153			
Conglomerate Sand	3,180			
Arbuckle	3,219			
RTD	3,225			
DST #1: Open 60" (30-30-30-30) Slide tool 5'. Recovered 80' slight oil cut mud. ISIP 202#, FSIP 191#, FFP 32-32#, FFP 53-53#.	2,862	2,885		
DST #2: Open 60" (30-30-30-30) Recovered 10' mud, no show.	3,131	3,195		
Decision to abandon at a depth of 3,225, six feet in the Arbuckle, was prompted as a result of poor, thin sand development in the Conglomerate section and structurally low Arbuckle.				
PLUGGED AND ABANDONED AT RTD	3,225			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

	Icer Addis <small>Signature</small>
	Owner-Operator <small>Title</small>
	February 24, 1976 <small>Date</small>