

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**508 EAST MURDOCK - WICHITA, KANSAS**

COMPANY **BENNETT & ROBERTS OIL OPERATIONS**

SEC. 27 T. 14 R. 12W  
 LOC. NE SW NW

FARM **Morris**

NO. 2

TOTAL DEPTH **3190**

COMM. **2-24-67**


COMP. **3-3-67**

SHOT OR TREATED

CONTRACTOR **Shields Drlg.**

ISSUED **4-15-67**

COUNTY **Russell**  
 KANSAS



CASING

|    |                        |
|----|------------------------|
| 20 | 10                     |
| 15 | 8 5/8" @ 313' w/180 sx |
| 12 | 6                      |
| 13 | 5                      |

ELEVATION **1658' KB**

PRODUCTION **DRY/CONG**

FIGURES INDICATE BOTTOM OF FORMATIONS

|                        |              |
|------------------------|--------------|
| Sand, shale, hard sand | 290'         |
| Shale                  | 320'         |
| Shale & shells         | 350'         |
| Shale                  | 579'         |
| Anhydrite              | 610'         |
| Shale & shells         | 950'         |
| Salt, shale & shells   | 1,260'       |
| Shale & lime           | 1,520'       |
| Lime                   | 1,650'       |
| Lime & shale           | 2,500'       |
| Lime                   | 3,190' R T D |

TOPS: **SAMPLE**

|                  |      |
|------------------|------|
| Anhydrite        | 529  |
| Topeka           | 2493 |
| Heebner          | 2733 |
| Toronto          | 2753 |
| Lansing          | 2820 |
| Base Kansas City | 3068 |
| Conglomerate     | 3106 |

DST #1 2,852'-70'

Tool open 30 min. Recovered 12' muddy water.  
 IBHP-857#, IFP-28#, FFP-38#, FBHP-820#