

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas


Company - GULF OIL CORPORATION
Farm - Abraham Heard No. 5

SEC. 30 T. 14 R. 12W
SE SW SW
330' N SL & 990' E WL SW $\frac{1}{4}$

Total Depth. 3325'
Comm. 8-1-48 Comp. 10-1-48
Shot or Treated. Acidized w/2000 gals. 10-1-48
Contractor.
Issued. 12-25-48

County. Russell

KANSAS



Distance H: Top cellar on 6" is 11' below rotary bushing.

CASING:

10-3/4" 636' Cem. w/300 Sx. left in
6" 3215' Cem. w/125 Sx. left in

Elevation. 1688 feet

Production. 171 BOPH, injection test. SWDN

Figures Indicate Bottom of Formations.

surface sand & clay 85
red bed 135
shale & shells 310
red bed 415
shale & shells 625
anhydrite 660
shale & shells 1225
salt & shale 1265
lime & shale 2120
shale 2330
lime & shale 2560
lime 2755
lime & shale 2835
lime 2905
lime & shale 2961
lime 3070
lime & shale 3115
lime 3155
lime, cherty, & sand 3180
lime sdy 3215
lime & sand 3259
lime sdy 3273
sand 3325
Total Depth

Tops:

Heebner 2748
Toronto 2769
Base Oread 2790
~~Base~~ Lime 2836
Lansing 2850
Base Kansas City 3105
Penn. Base Conglo. 3124
Pre Cambrian 3323