

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Kaps No. 2

SEC. 32 T. 14 R. 12W
CN/2 NW SW
330' S & 660' E of W $\frac{1}{4}$ Corner

Total Depth. 3181'
Comm. 4-18-48 Comp. 5-18-48
Shot or Treated.
Contractor. Holm Drlg. Co.
issued. 7-10-48

County. Russell
KANSAS



CASING:
8-5/8" 412' Cem. W/250 Sx.
5-1/2" 3176' Cem. W/150 Sx.

Elevation. 1733.9 feet.

Production. Pump 142 oil, no
wtr., 24 hours.

Figures Indicate Bottom of Formations.

shale	30
sand	50
shale & shells	160
sand & shale	270
shale	315
shale & shells	393
shale red	475
shale & red bed	645
sand	675
anhydrite	710
shale	830
shale & shells	930
shale	1080
shale & salt	1355
shale & lime	1415
lime & shale	1795
lime	1840
lime & shale	1930
shale	1945
lime brkn	2075
shale & lime	2180
shale & shells	2515
lime & shale	2665
lime	3183
3183 RTD = 3178 SLM	
lime	3181
Total Depth	

Tops:
Lansing Corr. 2889
Arbuckle Corr. 3175
Penetration 6

Fill-up:
100' oil in 1-3/4 hor. at 3178'
545' oil in 3 hrs 25 mins. at 3181'
715' oil in 3 hrs 55 mins. at 3181'
1350' oil in 6 1/2 hours.
1610' oil in 8 1/2 hours.
2175' oil in 16 1/2 hours