

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company CITIES SERVICE OIL COMPANY
Farm Steinle "B" No. 3

SEC. 32 T. 14 S. 12W
CN $\frac{1}{2}$ NW NW
330' S & 660' E of NW corner

Total Depth. 3162' SLM
Comm. 9-15-47 Contp. 9-25-47
Shot or Treated.
Contractor. Holm Drilling Company
Issued. 1-31-48

County. Russell
KANSAS



CASING:
8-5/8" 400' Cem. w/200 sx
5-1/2" 3159' Cem. w/125 sx

Elevation. 1718 act.

Production. Echo. Pot: 2565 BO &
435 BW, 24 hours.

Figures indicate Bottom of Formations.

clay & shale	0-20
shale & shells	100
sand & iron shells	160 ✓
shale & shells	175
iron	178 ✓
shale & shells	300
sand, shale & shells	355
shale & shells	400
shale red	665
anhydrite	695
shale red	710
shale & shells	1095
salt, shale & shells	1110
shale & salt	1325
lime & shale	1505
shale & shells	1705
lime brkn	1755
lime & shale	1980
shale & shells	2085
shale	2115
shale & shells	2325
lime	2335
lime & shale	2580
lime	2816
shale	2840
lime	2880
lime sft	2888
lime	2900
lime sft	2918
lime	2964
lime sft	2975
lime	2979
lime sft	2988
lime	3035
lime & shale brks	3070
lime	3164
3164 RTD = 3162 SLM	
Total Depth	

Tops:
Lansing corr. 2873
Gorham corr. 3158
Penetration 4

Fillup:
2230' oil in 45 mins.
2490' oil in 1 hour.
2885' oil in 2 $\frac{1}{2}$ hours.