


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AMERICAN PETROFINA CO. OF TEXAS
Farm- Geo. Rein No. 9

SEC. 17 T. 14 R. 13W
C WL SW

Total Depth. 2440'
Comm. 7-24-62 Comp. 7-28-62
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 12-22-62

County Russell
KANSAS



Elevation. 1838' DF

Production. INPUT WELL---30 BOPD

Figures Indicate Bottom of Formations.

COMPLETE DRILLER'S LOG NOT AVAILABLE

Core #1 2366' --- 2416'

2366-2367.5 Red & green shale
2367.5-2370 Fine grained sand carrying
a good odor & good oil saturation.
Bleeding oil. Core gassy.
2370-2370.5 green shale
2370.5-2374 Fine grained sand w/good oil
saturation & bleeding oil. Good odor.
Gassy.
2374-2379 Gray shale
2379-2380 Gray fossiliferous limestone.
2380-2386 Gray shale
2386-2387 Coal
2387-2393 Fine grained sand w/very thin
shale. Lamination. Good oil staining &
odor. Bleeding oil. Gassy
2393-2403 Gray shale w/thin sand stringers.
20 to 50% sand thru this section. Gassy.
Some oil staining.
2403-2416 Gray shale
50' cored & 50' recovered.
2440' RTD
Total Depth

TOPS: SAMPLE

Anhydrite (driller)	820
Grandhaven Lime	2357
Dry Shale (1st Tarkio Sand)	2368
Dover Lime	2379
Willard Shale (2nd Tarkio Sand)	2387

Completed for WTR INJECTION WELL 8-3-62