

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- AMERICAN PETROFINA CO. OF TEXAS
 Farm- Geo. Rein No. 10

SEC. 17 T. 14 R. 13W
 C S/2 S/2 SW

Total Depth. 2440'

Comm. 7-29-62


Comp. 8-2-62

Shot or Treated.

Contractor. Murfin Drilling Co.

Issued. 12-22-62

County Russell
 KANSAS



Elevation. 1842' DE

Production. INPUT WELL

CASING:

8 5/8" 209' cem w/150 sx.
 5 1/2" 2439' cem w/200 sx.

Figures Indicate Bottom of Formations.

COMPLETE DRILLER'S LOG NOT AVAILABLE

Core #1 2366-2416'

2366-2367' Red shale
 2367-2368' Green Shale
 2368-2369' Fine grained sand carrying good
 staining & saturation. Good odor. Bleeding
 oil & gas.
 2369-2370.5' Green shale.
 2370.5-2371' Fine grained sand. Fair odor.
 Bleeding some oil & gas. Fair saturation.
 2371-2372' Green & gray shale.
 2372-2375' Fine grained sand. Good saturation.
 Good odor. Bleeding oil & gas.
 2375-2379' Gray shale.
 2379-2381' Gray fossiliferous lime.
 2381-2386' Gray shale
 2386-2387' Coal
 2387-2388' Gray shale
 2388-2395' Fine grained sand carrying
 scattered saturation, & bleeding some
 oil. Very light odor. This section was
 shaly. Bleeding some gas.
 2395-2397' 50% shale & 50% sand as above.
 2397-2398' Gray shale.
 2399-2401' 70% gray shale & 30% fine
 grained sand. Laminated.
 2401-2413' Gray shale.
 2413-2416' Lost.
 50' cored & 47' recovered.
 2440' RTD
 Total Depth

TOPS: SAMPLE

Anhydrite (driller)	798
Grandhaven Lime	2358
Dry Shale (1st Tarkio Sand)	2368
Dover Lime	2379
Willard Shale (2nd Tarkio Sand)	2388