


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - MURFIN, LINDAS, & MARSHALL  
Farm - Rein "C" No. 2

SEC. 17 T. 14 R13W  
SE NE SW

Total Depth. 2440  
Comm. 5-8-50 Comp. 6-17-50  
Shot or Treated.  
Contractor. Murfin Drilling Co.  
Issued. 8-26-50

County. Russell  
KANSAS



1854(m)  
Elevation. 1855

Production. 40 BOPD

CASING:

10" 507'  
8 1/4" 825'  
6 5/8" 2389'

Figures Indicate Bottom of Formations.

yellow clay 19  
blue shale 150  
sandy shale 160  
gray shale 175  
brkn sand 185  
gray shale 195  
brkn sand 205  
gray shale 215  
yellow shale 220  
brown shale 228  
yellow shale 240  
sand 245  
red rock 280  
blue shale 290  
red rock 330  
blue shale 335  
gray sandy shale 350  
blue shale, shells 353  
sand 359  
blue shale 377  
water sand 390  
blue shale 465  
iron, lime 472  
gray shale 475  
blue shale 500  
red shale 509  
red rock 635  
red shale 695  
red rock 765  
red shale 816  
anhydrite lime 853  
red rock 1006  
blue shale 1055  
red rock 1115  
blue shale 1175  
slate, shells 1213  
salt 1495  
lime 1500  
blue shale 1515  
shale, shells 1575  
lime 1585  
gray shale 1595  
lime 1618  
red rock 1623  
blue shale 1628  
lime 1657  
blue shale 1663  
lime 1670  
red rock 1675  
lime 1710  
blue shale 1718  
red rock 1745  
lime 1825  
broken lime 1855  
lime-sharp 1875  
blue shale 1880  
red rock 1887  
lime 1920  
blue shale 1928  
lime 1945  
blue shale 1960

shale 1965  
lime 2010  
red rock 2020  
lime broken 2033  
lime sandy 2050  
blue shale 2054  
lime 2085  
red rock 2094  
lime 2150  
blue shale 2155  
red rock 2169  
broken lime 2205  
lime 2240  
blue shale 2260  
shale, shells 2263  
lime sandy 2270  
shale, shells 2275  
blue shale 2285  
lime 2292  
dark shale 2297  
lime hard 2303  
blue shale 2305  
blue shale, shells 2375  
lime 2386  
red rock 2389  
sand-Tarkio 2400  
sandy lime, shale 2405  
sand 2417  
blue shale 2425  
sand 2427  
shale 2440  
Total Depth

Tops:  
Tarkio 2389-2417

5 BW 195-205 HFW 390