


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

SKELLY OIL CO.
T.B.Carter No. 1.

Plotted Texts CO.
SEC. 33 T. 14 R. 13W
CNE 8 1/2 S 1/2 NE SW NE
460' fr SL 660' fr WL NE 1/2

Total Depth. 2869 1/2
Comm. 2-25-39 Comp. 3-19-39
Shot or Treated. 1000, 4000, 4000 Gal Acid.
Contractor. Claude Drilling Co.
Issued. 5-20-39

County Russell.



CASING.

Rotary 2860
Cable 2869 1/2
13" 257'
65/8" 2860'

Elevation

Production. Pot. 524 B.

Figures Indicate Bottom of Formations.

sand	50	lime grey	2869 1/2
red rock	90	Total Depth.	
lime	105		
sand	130	Top Lansing lime	2821 SLM
sand and pyrites of iron	312		
red rock	610	oil 2845-2850	
lime and anhydrite	645	oil 2860-2869 1/2	Main body pay formation.
anhydrite hard	655		
red rock and shells	988	March 23, 1939	1000 gal acid 2860-2869 1/2
shale and shells	1160	March 24, 1939	4000 gal acid 2860-2869 1/2
salt	1200	March 26, 1929	4000 gal acid 2845-2850
shale and salt	1275		
broken lime hard	1370		
lime	1580		
broken lime	1647		
lime	1677		
shale and shells	1793		
broken lime	1882		
lime	1936		
broken lime	2215		
shale and shells	2325		
shale and lime	2360		
broken lime	2485		
shale and shells	2565		
lime	2648		
shale and shells	2675		
broken lime	2726		
lime	2774		
steel line correction	2782		
lime	2792		
sdv shalo	2816		
Cored 2816-2835	Rec 4 1/2'		
Top	3' Dark grey shalo		
btm	1 1/2' lime dark grey		
hard grey crystalline and			
cherty lime	2847		
limo grey	2849		
porous and light sat.			
cored 2849-2862	Rec 13'		
Top	3' Brown porous oolitic limo sat.		
	6' grey limo with shalo strks		
	2' dark grey shaley limo		
	1' green shale		
Btm	1' Grey Porous lime Stained no sat.		
Steel line correction rotary table			
to derrick floor.	2863- 2860		
lime grey oolitic	2865 soft porous and oil stained		
	show free oil		
grey lime	2868 Porous & slightly oil stained. no increase		
	in oil		