

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **GENE HUEBNER**
Farm- **Hefferman**

No. **3**

SEC. **33** T. **14** R. **13W**
SW NW SW

Total Depth. **2250 PB 2240**

Comm. **10-5-51**

Comp. **11-7-51**


County **Russell**

KANSAS

Shot or Treated.

Contractor.

Issued. **12-8-51**



CASING:

15 1/2" 80' P. 40'

12 1/2" 320' P.

10" 660' P.

8 1/4" 2040' P.

5 1/2" 2233' com. w/100 sx

Elevation. **1701 DF**

Production. **50 BOPD**

Figures indicate Bottom of Formations.

cellar	10	lime	1663	Plugged back 2240'
sand	65	shale	1665	Good show gas - 2226-30'
shale blue	75	lime	1695	Good show oil - 2233-38'
sand & iron	85	lime sharp	1705	HFW @ 30'
sand	95	shale	1710	Sand & Pyrite 75-125'
iron	125	red rock	1718	Sand & Pyrite 170-178'
shale gry	170	lime	1740	Iron Pyrite 257-259'
sand & iron	178	shale	1745	Iron Pyrite 290-300'
shale blue	183	slate	1748	1-1/2 BWPB 500-520'
sand	225	lime	1775	1/2 BWPB 1055-1065'
shale blue	230	slate	1780	Small show gas 1630-1640'
slate blk	243	shale	1790	1 BWPB 1900-1910'
sand	257	lime broken	1815	
iron	259	lime	1844	Drilled with Shields'
slate blue	275	red rock	1848	Cable tools.
shale blue	285	lime	1860	
sand	290	slate	1865	
sand & iron	300	lime	1910	
shale	310	shale	1920	
sand	318	red rock	1926	
red rock	645	lime	1975	
anhydrite lime	660	shale blue	1990	
lime	678	lime	1995	
red rock	855	red rock	2003	
slate blue	885	lime	2014	
shale blue	895	shale	2030	
red rock	955	lime	2045	
shale blue	975	shale blue	2055	
red rock	980	lime	2062	
shale blue	995	shale	2070	
slate blue	1025	lime	2074	
lime	1030	shale	2090	
slate	1055	lime	2096	
salt	1290	shale	2100	
shale	1300	lime broken	2110	
lime	1310	slate	2123	
shale	1315	lime	2126	
lime	1350	slate	2130	
slate	1357	shale & shells	2150	
lime	1375	lime	2165	
shale blue	1385	shale & shells	2165	
lime	1387	lime	2168	
red rock	1392	shale blue	2176	
lime	1400	shale red	2180	
shale	1405	red rock	2186	
lime hrd	1425	sandy shale	2196	
lime	1440	lime	2203	
red rock	1443	slate brown	2218	
lime broken	1455	lime	2224	
lime	1485	shale	2226	
shale gry	1505	tarkio sand	2238	
shale	1510	sandy shale	2250	
lime, sandy	1540	Total Depth PB 2240		
shale	1545			
slate	1550	Tops:		
red rock	1565	Anhydrite	645	
lime	1605	Salt	1055	
shale	1615	Tarkio	2226	