

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167-19449-0001

245 North Water
Wichita, KS 67202

Operator's Full Name Genevieve R. Hall Trust #1 et al

Complete Address P. O. Box 191, Russell, Kansas 67665

Lease Name E. Miller "A" Well No. 4

Location SW SW SE Sec. 30 Twp. 14S Rge. 13 (~~13E~~) (West)

County Russell Total Depth 2980'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co Tools & Allied Cementing Co.

Address Box 191, Russell, Kansas 67665 License No. _____

Operation Completed: Hour 11:30 Day 4 Month 12 Year 1980
AM

The above well was plugged as follows:

Squeezed thru 15 1/2" and 8 5/8" and 6 5/8" casing with 100 sx
cement, 2 sx hulls, 25 sx mud-gel, 2 sx hull, and 200 sx cem.

Max. pres. 1000#. Shut in pres. 400#.

No casing recovery.

76 joints of 2 1/2" tubing left in hole, top of tubing at 700'.

91 joints of rods left in hole, top of rods at 700'.

40' of 15 1/2" surface casing no cement.

8 5/8" casing ??

2875' of 6 5/8" casing cement ??

DEC - 8 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane Rankin
Conservation Division Agent

DATE 1-12-81

INV. NO. 3853-W


15-167-19449-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

30



Locate well correctly on above
Section Plat

Russell County. Sec. 30 Twp. 14S Rge. 13W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SW SW SE
Lease Owner Genevieve R. Hall Trust #1 et al
Lease Name E Miller A Well No. 4
Office Address P.O. Box 191, Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)
Oil
Date Well completed September 27 19 35
Application for plugging filed October 6 19 80
Application for plugging approved October 8 19 80
Plugging commenced December 4 19 80
Plugging completed December 4 19 80
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production
May 25 19 56

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Duane L. Rankin
Producing formation Lansing Depth to top 2885 Bottom Total Depth of Well 2980
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
-----------	---------	------	----	------	--------	------------

See attached log for casing record and oil, gas & water records

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Squeezed thru 8 5/8" & 6 5/8" with 100 sacks cement & 2 sacks hulls
then 25 sacks gel and 2 sacks of hulls.
then 200 sacks to top (100 sacks cement and 100 sacks pozmix. 3% cal chloride & 4% gel)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Donald H. Beck

STATE OF Colorado COUNTY OF Jefferson ss.

Carl W. Fulkerson

(employee of owner) or (representative) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Carl W. Fulkerson

P. O. Box 15247, Lakewood, Colorado 80215
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December 19 80

My Commission Expires May 22, 1983

My commission expires

Emilie Carlson

Notary Public.