


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- KESSLER & SCHMIDT
Farm- Lewis No. 2

SEC. 10 T. 14 R. 13W
SE SW SW

Total Depth. 2400'
Comm. 6-17-54 Comp. 6-23-54
Shot or Treated.
Contractor.
Issued. 3-17-56

County Russell
KANSAS



Elevation. 1817' DF

Production. 25 BO & 50% wtr.

Figures indicate Bottom of Formations.

NO LOG AVAILABLE

Tops: KB Meas.
Anhydrite 789
Grandhaven 2341
Firs Sand Tarkio 2356
RTD 2400

Following is a description of the cored interval:

2349-51 Gray shale
2351-54 Red shale
2354-56 Green shale
2356-57 Slight show of oil green sandy micaceous shale
2357-58 Show of oil green micaceous partly shaly sandstone. Odor.
2358-59 Show of oil green fine grained micaceous slightly shaley sandstone. Odor.
2359-60 Light saturation pale green very fine grained sandstone. Odor.
2360-64 Saturation green fine grained micaceous sandstone. Porosity. Odor.
2364-69 Gray shale.
2369-71 Brown to grey hard dense fossiliferous limestone.
2371-74 Gray shale
2374-75 Black coal.
2375-83 Gray shale.
2383-89 Thin white to gray sand laminations within gray shale. No show.