

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- LOUIS M. MAI
Farm- Paul Dumler No. 5

SEC. 16 T. 14 R. 13W
SW NE SW

Total Depth. 2414'
Comm. 5-5-55 Comp. 6-16-55
Shot or Treated.
Contractor. Louis M. Mai
Issued. 8-15-59

County Russell
KANSAS



CASING:
15½" 30' P. 8½" 805' P.
12½" 340' P. 7" 2408' cem w/50 sx.
10 3/4" 513' P.

Elevation. 1860' DF

Production. 10 BOPD

Figures Indicate Bottom of Formations.

cellar	10
yellow clay	12
post rock	19
yellow clay	30
blue shale	180
sand	186
shale	240
sand	246
red rock	253
gray shale	275
red rock	280
sand	325
lime	330
red rock	340
sand & shale	505
red rock	802
Anhydrite	841
red rock	1000
shale blue	1038
red rock	1115
shale blue	1175
shale & lime shells	1200
salt	1468
shale & shells	1530
lime & shale	1700
red rock	1730
lime & shale	1900
lime	1940
lime & shale	1974
red rock	1985
lime	2000
red rock	2005
lime sandy	2050
red rock	2065
lime & shale	2125
red rock	2135
lime & shale	2180
lime	2210
lime & shale	2285
Hole Corrected	2285-2321'
lime & shale	2345
lime	2365
shale gray	2374
lime, light gray	2383
red rock	2389
shale, green	2391
sand	2395
shale gray	2398
shale & lime	2410
sand	2414
Total Depth	
TOPS: SCOUT	
Tarkio	2390