

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
 Farm- Chester Bear No. 2

SEC. 16 T. 14 R. 13W
 NW NW NW

Total Depth. 2438; PB 2416
 Comm. 2-8-55 Comp. 3-9-55
 Shot or Treated.
 Contractor. Earl F. Wakefield
 Issued. 4-9-55

County Russell
 KANSAS



Elevation. 1871 DF

Production. 48 BO & 9 BW/24
 hrs.

CASING:
 15 1/2" 396' Pulled
 13 3/8" 510' "
 10 3/4" 819' cem. w/950 sx, circ.
 7" 2437' cem. w/200 sx
 Figures indicate Bottom of Formations.

cellar	8	lime	2050
yellow clay	38	shale	2055
blue shale	225	lime	2075
red shale HFW	290	1/2 BW 2060-70	
sand	325	shale	2102
blue shale	340	lime	2130
redrock	350	blue shale	2135
blue shale	357	lime	2160
sand	375	shale	2170
shale	390	lime	2190
sand	396	shale	2207
blue shale	435	lime	2245
sand	470	blue shale	2255
blue shale	484	shale & shells	2315
shale	505	Correction 2315 equals	2328
redrock	815	shale	2348
3 BWPH 670-680		lime	2365
Anhydrite	853	shale	2394
redrock	1005	lime	2398
blue shale	1055	shale	2407
redrock	1100	sand (Tarkio)	2412
shale	1120	shale	2425
redrock	1135	sand	2438
blue shale	1210	Total depth; PB	2416
salt	1485		
shale	1490	Scout Top:	
lime	1505	Tarkio	2407
salt	1515		
shale	1520		
lime	1535		
lime & shells	1640		
lime	1655		
shale	1660		
lime	1675		
shale	1695		
lime	1730		
shale	1735		
redrock	1760		
lime	1865		
lime (sharp)	1875		
lime	1890		
redrock	1895		
lime	1920		
shale	1928		
lime	1935		
shale	1945		
lime	1950		
shale	1960		
lime	2015		
redrock	2020		