

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- MURFIN DRILLING COMPANY
 Farm- Rein "B" No. 6

SEC. 18 T. 14 R. 13W
 NE SE SW

Total Depth. 2351
 Comm. 2-7-53 Comp. 3-13-53
 Shot or Treated.
 Contractor. Murfin Drlg. Co.
 Issued. 6-6-53

County Russell
 KANSAS



Elevation. 1803

Production. Pmp. 30 bbls.

CASING:

15 1/2" 26' 8 5/8" 780'
 12 1/2" 321' 7" 2343 1/2'
 10" 460-20'

Figures indicate Bottom of Formations.

cellar	9	shale blue	2250
yellow clay	21	lime	2255
sand	25	shale blue	2260
shale blue	115	lime & shale	2265
shale gry	132	shale blue	2270
shale brown	180	lime	2275
shale gry	185	shale blue	2280
shale brown	205	shale & shells	2295
shale blue	255	red rock	2300
shale brown	285	shale & shells	2310
shale gry	290	lime sandy	2320
shale blue	300	shale brown	2324
sand, water	310	top Tarkio	2329
shale gry	325	shale gry	2336
sand & water	335	red lime, shell	2338
shale blue	370	shale blue	2343
shale brown	380	Tarkio sand	2351
shale blue	420	Total Depth	
shale gry	425		
shale brown	438	Tops: Scout	
shale Dakota	770	Anhydrite	780
anhydrite wet	795	1st Tarkio	2324
shale brown	865	2nd Tarkio	2343
red rock	955		
shale blue	1025		
red rock	1065		
shale blue	1165		
salt	1265		
salt, broken	1450		
lime broken	1535		
lime hrd	1555		
red rock	1560		
lime broken	1570		
lime sandy	1595		
shale blue	1695		
lime	1650		
red rock	1670		
lime	1800		
shale blue	1810		
red rock	1820		
lime broken	1990		
lime	2023		
red rock	2038		
lime	2055		
red rock	2065		
lime	2115		
shale blue	2142		
lime	2165		
red rock	2175		
lime	2180		
red rock	2190		
shale & shells	2200		
lime	2210		
shale & shells	2225		
shale blue	2330		
lime broken	2238		