


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CORALENA OIL CO.
Clyde No. 3

SEC. 19 T. 14 R. 13 W.
CSL NW SW

Total Depth. 2982
Comm. 6-8-42 Comp. 6-20-42
Shot or Treated.
Contractor.
Issued. 8-8-42

County Russell.



CASING.

10 3/4" 190'
7" 2982'

Elevation.

Production. Pot. 72 B.
Physical

Figures Indicate Bottom of Formations.

| | |
|-----------------------------------|--|
| lime shells | 252 |
| sand and shale | 290 |
| shale and shells | 720 |
| anhydrite | 760 |
| shale and shells | 1110 |
| salt | 1366 |
| shale and shells | 1510 |
| lime and shale | 1775 |
| lime | 1925 |
| shale | 1932 |
| lime | 2005 |
| lime and shale | 2095 |
| lime, shale and shells | 2180 |
| lime and shale | 2650 |
| SLM at 2540 OK | |
| lime grey | 2785 |
| lime soft | 2790 Spotted to fair saturation. |
| lime grey and shale blk and green | 2843 |
| lime white | 2865 Spotted saturation. |
| shale red, blue and green | 2896 |
| lime grey | 2900 some saturation - little porosity. |
| lime white to grey | 2914 |
| lime | 2918 spotted to good saturation. |
| lime hard | 2922 |
| lime | 2924 spotted to good saturation. |
| lime grey | 2933 |
| lime soft | 2940 spotted to good saturation. Porosity. |
| lime | 2982 |
| Total Depth. | |

Tops - Topeka 2650
Dodge 2843
Kansas City 2896