

STEARNS DRILLING CO. ET AL.
Opdyke No. 3.


SEC. 20 T. 14 R. 13 W.
CS $\frac{1}{2}$ SW SW

Total Depth. 3014
Comm. 9-3-41 Comp. 10-8-41
Shot or Treated. 3000 gal.
Contractor.
Issued. 1-3-42

County Russell.

CASING.

20" 59'5" Left in.
15 $\frac{1}{2}$ " 253' 4" Pulled.
13 $\frac{3}{8}$ " 418' Pulled.
10" 715'
8 $\frac{5}{8}$ " 2411'
7" 2919'1" left in.



Elevation.

Production. Pot. 361 B.

Figures Indicate Bottom of Formations.

cellar	10	limo	1970
sand	50	shale blue	1975
shale light	65	red rock	1995
red rock	80	limo	2045
shale blue	95	shale red	2050
red rock	115	lime	2065
shale light	170	shale and shells	2155
sand	200 HFW	lime	2165
shale blue	220	shale blue	2175
red rock	235	lime	2185
sand	240	shale and shells	2200
shale blue	251	shale blue	2220
shale grey	290	limo	2245
sand	310 HFW	shale and shells	2295
shale blue	340	shy shale	2300 SO
sand	355	shale and shells	2330
shale blue	405	lime	2345
red rock	712	shale blue	2400
lime	750	lime	2420
red rock	915	shale light	2425
shale blue	965	shale shells	2515
red rock	1025	lime	2550
shale grey	1060	shale blue	2555
shale blue	1125	lime	2560
salt	1370	shale blue	2565
shale blue	1390	lime	2595
lime	1415	shale blue	2612
shale grey	1430	lime	2645
lime	1455	shale	2650
shale blue	1465	lime	2835
shale brown	1470	shale blk	2838
lime	1500	lime	2846
shale grey	1515	shale	2855
lime	1525	lime	2875
shale brown	1530	shale blue	2877
lime	1625	shale brown	2882
shale red	1635	shale green	2908
shale brown	1650	lime SLM 2908 equals	2914
lime	1660	lime	2928
shale and shells	1670	shale blue	2935
shy shale	1685 show gas	lime	2947
lime	1760	lime soft	2952 sh oil
shy lime	1775	lime	2978
shale brown	1790	lime soft	2983 Sh oil
lime	1800	lime	2984
shale grey	1820	shale	2987
lime	1835	lime	2995
shale blue	1840	shale blue	2998
lime	1850	lime hard	3004
shale and shells	1860 show gas.	lime soft	3009 sh oil
lime	1900	lime	3014
red rock	1910	Total Depth.	
lime	1940		
shale and shells	1950		