

CORALENA OIL CO.  
 Graham No. 1.

SEC. 21 T. 14 R. 13W  
 CSL SW SE

Total Depth. 3011'  
 Comm. 3-2-40 Comp. 4-20-40  
 Shot or Treated.  
 Contractor.  
 Issued. 5-11-40

County. Russell



CASING:  
 10 $\frac{1}{2}$ " 205'  
 5 $\frac{1}{2}$ " 2970'

Elevation.

Production. Pot. 145 B.

Figures Indicate Bottom of Formations.

shale & shells	250
shale	258
shale & shells	655
shale	695
anhydrite & lime	737
shale & shells	1140
salt	1340
shale & shells	1390
shale & lime	1785
lime	1810
shale & lime	2110
shale	2240
shale & shells	2415
shale & lime	2646
lime	2715
shale & lime	2725
lime	2843
shale	2860
lime SLM @ 2870	2870
lime white-saturation	2880
lime white, some saturation-tight	2885
lime white & shale, some saturation-tight	2891
cored 15' recovery	2891-2909
shale	2891-2900
lime-slight saturation	2910
lime w/shale strks	2915
shale green & red	2922
lime-oil	2934
lime & shale	2940
lime white	2967
cored lime w/strks of shale	2983
lime white	2998
core white lime sft porous, stain	3011
Total Depth.	

Top Topeka Lime 2646  
 Top Dodge 2855  
 Top Kansas City 2900

Perforations:

2921-25 with 12 shots  
 2925 $\frac{1}{2}$ -29 $\frac{1}{2}$  with 12 shots  
 2928-31 with 12 shots