


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

CITIES SERVICE OIL CO.
Weimeister No. 1.

SEC. 25 T. 14 R. 13W.
SEc SW
330' N. 330' W of S $\frac{1}{4}$ corner.

Total Depth. 3105
Comm. 3-22-41 Comp. 4-11-41
Shot or Treated. None.
Contractor. R.W.Rine Drilling Co.
Issued. 5-17-41

County Russell.



CASING.

85/8" 355' cemented.
5 $\frac{1}{2}$ " 2829' cemented.
4 $\frac{1}{2}$ " set 339' 8" liner at 3103'

Elevation.

Production. Pot. 413 B.O.
1% wtr. Physical.

Figures Indicate Bottom of Formations.

surface sand	40
shale and shells	460
red bed	605
red bed and shale	1215
shale and shells	1434
shale and lime	1774
shale and shells	2050
shale	2520
lime broken	2536
lime and shale	2810
lime	2828
Rot. T.D. 2828 equals	2830 SLM.
lime	2877
shale break	2884
lime	2885
broken lime soft	2898
lime white	2907
lime small sh oil&wtr	2911
lime	2956
broken lime	2962
lime	2971
broken lime	2976
lime	2997
broken lime 2 BWPH	3005
lime	3022
shale	3035
lime	3073
shale	3083
lime	3092
shale	3096
lime	3105
Total Depth.	show oil 3100-05

Corr. Top Lansing 2809
Top Arbuckle 3101
Penetration 4'

Bailed 5-6 bailers oil per hr
filled 300-2850' in 16 hours.