


CONTINENTAL OIL CO.
 Bunker Hill Bank No. 1.

SEC. 26 T. 14 R. 13W
 SWc NE
 330'N 330'E Center

Total Depth. 2940'
 Comm. 3-6-39 Comp. 4-5-39
 Shot or Treated. 3000 gal.
 Contractor. Parker Drlg.Co.
 Issued. 6-24-39

County. Russell



CASING:
 10³/₄" 343'
 7" 2892'

Elevation.

Production. Pot. 3614.43 B.
 No wtr.

Figures Indicate Bottom of Formations.

cellar	12
sand	35
shale & shells	197
wtr sand	223
sand hrd	265
red bed & sand shells	270
sand hrd	280
sand	289
shale & shells	305
sandstone	323
shale & shells	350
shale & shells	395
red beds & shells	668
anhydrite	707
shale & shells	1110
shale & salt	1285
shale & lime shells	1355
brkn lime & shale	1673
sand	1685
lime brkn	1719
lime brkn & shale	1938
lime	1952
lime brkn & shale	2137
shale & shells	2210
shale & lime shells	2365
lime brkn	2388
shale & lime brkn	2572
lime Topeka	2595
lime	2696
lime brkn	2742
lime	2772
lime & shale	2839
lime	2850
brkn lime & shale	2875
lime K.C.	2940
Total Depth.	

Total Depth from cement
 floor level 2939'
 Total fillup with oil 2450'

Well acidized w/3000 Gals.
 4-13-39 on initial potential
 test the well pumped 1204.81
 BO in 8 hrs, giving the well
 a 24-hr potential of 3614.43
 BO, no water

Topeka lime 2571-2594
 Kansas City lime 2873-2939
 Measurements from cement
 floor level.