

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

CONTINENTAL OIL CO.
William Letsch No. 5.

SEC. 26 T. 14 R. 13W
CEL W/2 SW
990' E 1320' S W/4 Cor.

County. Russell

Total Depth. 2850'
Comm. 2-13-38 Comp. 3-7-38
Shot or Treated. 7000 Gals.
Contractor. Parker Drlg. Co.
Issued. 6-11-38



CASING:
10 $\frac{5}{8}$ " 300'
7" 2814'

Elevation.

Production. Pot. 3240 B.

Figures Indicate Botb m of Formations.

cellar	38
sand & shale	188
iron pyrite	196
shale & shells	304
shale	335
red rock shale & shells	603
anhydrite	645
red rock & red bed	837
red bed shale	1130
salt & shale	1240
brkn lime & shale	1370
brkn lime	1380
lime hrd	1450
lime	1570
brkn lime	1700
lime	1800
brkn lime & shale	2015
lime & shale	2135
brkn lime	2170
shale & shell	2376
lime & shale	2460
lime	2486
Steel tape correction 2486-2483	
lime	2483-2532
lime hrd	2579
lime	2758
lime & shale	2785
shale	2797
Top Kansas City lime 2796	
lime Kansas City	2808
lime	2849
shale	2850
Total Depth.	

The plug was drilled and well filled up
300' with oil 2 hrs. Before acidizing
well had filled up to 1900' with oil.
On 30 min. pumping test after acidizing
well pumped 76 bbls oil.