

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
Wm. Letsch No. 9

SEC. 26 T. 14 R. 13W.
SW SE SW
330' N. & 990' W of S $\frac{1}{4}$ cor.

Total Depth. 2875
Comm. 10-25-38 Comp. 11-14-38
Shot or Treated. 7000 gal acid.
Contractor.
Issued. 12-31-38

County Russell.



CASING.

103/4" 315' 7" 2828'

Elevation.

Production/ Pot. 2491 B.

Figures Indicate Bottom of Formations.

cellar	8
surface soil and sand	50
clay and shalo	108
white rock	147
shale blue and shells	330
red bed and shalo	617
anhydrite	648
red bed	675
shalo and shells	1042
shale	1050
salt	1265
shale and shells	1354
limo and shalo	1399
shale and shells	1494
shale and limo	1595
shale and shells	1638
sand	1650
shale and limo	1695
shale and shells	1835
limo and shalo	1928
shale and shells	1996
limo and shalo	2095
shale and shells	2235
limo	2250
shalo and shells	2295
shale and limo	2559
limo	2685
broken limo and shalo	2716
limo	2746
limo and shale	2815
limo Kansas City	2834
limo	2875
Total Depth.	

Top Kansas City limo 2814

The well was drilled to a total depth of 2875 and filled up 1900' with oil. No pumping test on well before acidizing.

Nov 18, 1938. On initial Potential test after acidizing, the well pumped 830.48 bbls of oil in 8 hours, giving the well a twenty four hour potential of 2491 bbls of oil no water.