


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

CONTINENTAL OIL CO.
Wm. Letsch No. 11

SEC. 26 T. 14 R. 13W
SE NE SW
1155' S 330'W Center

County. Russell

Total Depth. 2872'
Comm. 10-31-39 Comp. 11-19-39
Shot or Treated. 500 Acid.
Contractor. Parker Drlg. Co.
Issued. 1-13-40



CASING:
10 3/4" 341'
6 " 2828'

Elevation.

Production. Pot: 1818 B.
No wtr

Figures Indicate Bottom of Formations.

cellar	9
surface soil	25
shale	75
shale & shells	136
lime sdy	168
lime & iron	258
shale & lime	350
shale & shells	420
red bed	612
anhydrite	645
shale & shells	800
lime	855
brkn lime & shale	1005
shale & salt	1240
shale & lime shells	1630
sand	1643
shale & lime shells	1770
lime brkn	1860
shale	1895
lime brkn	1930
shale & lime shells	2040
shale & shells	2320
lime	2360
shale & shells	2463
lime brkn	2515
lime	2735
shale & lime	2775
shale	2813
lime	2830
lime hrd	2833
lime	2871
shale	2872
Total Depth.	

Total depth from cement floor
level 2871'
Kan. City lime from cement floor
level 2810' to 2871'
Total fillup w/oil 1800'
11-21-39 acidized w/5000 Gals.
11-24-39 on initial potential
test well pumped 606.16 BO in
8 hrs giving the well a 24-hr
potential of 1818 BO., no wtr.