


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

MID CONTINENT PETROLEUM CORP.
William Letsoh No. 6

SEC 26 T. 14 R. 13W.
NE SE NW
990' S. & 330 fr E.L. NW $\frac{1}{4}$

Total Depth. 2900
Comm. 3-22-39 Comp. 4-26-39
Shot or Treated.
Contractor. Mac and Stauffer.
Issued. 6-3-39

County Russell



Elevation.

Production Pot. 1411 B.

CASING.

13" 193'5"
7" 2874'

Figures Indicate Bottom of Formations.

soil	4
clay	30
clay and shells	60
clay	152
sand rock	178
lime	236
shale and shells	325
clay and shells	410
red rock and shells	650
anhydrite	690
shale	767
shale and shells	909
anhydrite	934
shale shells and salt	1150
salt and shells	1300
shale and shells	1445
lime broken	1551
shale and lime	1660
lime broken	1725
shale and shells	1754
lime broken	1862
lime and shale	1966
lime broken	2155
shale and lime	2277
lime shells and shale	2345
lime broken	2445
shale and shells	2505
lime	2532
shale	2548
lime	2570
lime Topeka	2650
lime broken	2654
lime	2835
shale	2842
shale	2857
lime K.C.	2867
shale blk	2869
shale red	2872
shale green	2875
lime broken	2874
Lime K.C.	2876 little sat.
lime K.C.	2887 no sat.
lime K.C.	2890 drilled
lime K.C.	2900 Cored.

Total Depth.

Top Kansas City 2857