


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- MID-CONTINENT PETRO. CORP.
Farm- Wm. Letsch No. 12

SEC. 26 T. 14 R. 13W
NE NW NW

Total Depth. 2320
Comm. 4-7-52 Comp. 4-13-52
Shot or Treated. 180 shots
Contractor. Barnett Drlg. Inc.
Issued. 6-7-52

County Russell
KANSAS



Elevation. 1708

Production. 35 BOPD

CASING:

8 5/8" 220'
5 1/2" 2325'

Figures indicate Bottom of Formations.

sand & shale	85
sand	105
shale & shells	155
shale	370
red bed	395
red bed & shale	640
anhydrite	645
lime & shale	1475
lime	1685
shale & shells	1805
lime	1965
shale & lime	2190
lime	2205
sandy shale	2210
sand & shale, stained	2215
shale & sand	2220
sandy shale	2250
lime & sandy shale	2275
sandy shale	2291
lime, sand & shale	2320
Total Depth	
Scout Tops:	
Tarkio	2206