


TEXON OIL & LAND CO.
 William Letsch No. 2.

SEC. 26 T. 14 R. 13W
 SW NW SW
 330' E 990' S of W $\frac{1}{4}$ Cor.

County, Russell

Total Depth. 2940'
 Comm. 9-10-37 Comp. 10-6-37
 Shot or Treated. 7000 Gals.
 Contractor. Parker Drlg. Co.
 Issued. 12-4-37



Elevation.

CASING:
 10 $\frac{3}{4}$ " 282'5"
 7 " 2818'

Production. Pot. 2601 B.

Figures Indicate Bottom of Formations.

cellar	9
Top soil	40
sand	55
shale & shells	395
red bed & shale	628
anhydrite	648
shale & shells	1038
salt	1258
shale & lime shells	1325
shale & brkn lime	1447
lime	1500
shale & lime shells	1625
shale & lime	1650
sand	1665
shale & brkn lime	1687
shale & shells	1772
brkn lime	1855
shale & brkn lime	2036
Top K.C. lime	2804
shale & shells	2236
brkn lime & shale	2390
shale & shells	2495
shale	2509
brkn lime	2532
lime	2740
brkn lime & shale	2811
lime	2860
lime hrd	2887
lime	2940
Total Depth.	

On a potential test the well pumped 433.50 bbls. of oil the first four hours and 598.50 bbls of oil the last four hours of the test. Making a twenty-four hour potential test of 2601 bbls.